
Masters Theses

Student Theses and Dissertations

Summer 2012

Investigation of the effects of shrinkage, creep, and abrasion on self-consolidating concrete and high volume fly ash concrete for use in transportation related infrastructure

Brian Timothy Tucker

Follow this and additional works at: https://scholarsmine.mst.edu/masters_theses



Part of the [Civil Engineering Commons](#)

Department:

Recommended Citation

Tucker, Brian Timothy, "Investigation of the effects of shrinkage, creep, and abrasion on self-consolidating concrete and high volume fly ash concrete for use in transportation related infrastructure" (2012).

Masters Theses. 6899.

https://scholarsmine.mst.edu/masters_theses/6899

This thesis is brought to you by Scholars' Mine, a service of the Missouri S&T Library and Learning Resources. This work is protected by U. S. Copyright Law. Unauthorized use including reproduction for redistribution requires the permission of the copyright holder. For more information, please contact scholarsmine@mst.edu.

INVESTIGATION OF THE EFFECTS OF SHRINKAGE, CREEP, AND ABRASION
ON SELF CONSOLIDATING CONCRETE AND HIGH VOLUME FLY ASH
CONCRETE FOR USE IN TRANSPORTATION RELATED INFRASTRUCTURE

by

BRIAN TIMOTHY TUCKER

A THESIS

Presented to the Faculty of the Graduate School of the
MISSOURI UNIVERSITY OF SCIENCE AND TECHNOLOGY

In Partial Fulfillment of the Requirements for the Degree

MASTER OF SCIENCE IN CIVIL ENGINEERING

2012

Approved by

John J. Myers, Advisor
Jeffery S. Volz
David N. Richardson

ABSTRACT

Concrete specimens were fabricated for shrinkage, creep, and abrasion resistance testing. Variations of self-consolidating concrete (SCC), high volume fly ash concrete (HVFA), and conventional concrete were studied. The results were compared to previous similar testing programs and used to determine the adequacy of the materials for use in practice.

These two concrete variations offer significant benefits when used as replacements to conventional concrete. Because of the respective properties of both types of concrete, both economic and environmental benefits are achieved with the use of both. The lower labor costs of SCC and the lower material cost of HVFA lead to lower overall construction costs, while the decrease in CO₂ production and conservation of landfill space through the use of HVFA lead to significant environmental benefits. The SCC testing program consisted of normal strength (6000 psi) and high strength (10,000 psi) variations of SCC and conventional concrete. The HVFA testing program consisted of two variations of HVFA with 70% fly ash replacement and one conventional concrete mix.

All specimens were tested for compressive strength, modulus of elasticity, shrinkage strain, creep strain, and abrasion resistance. All tests were performed according to their respective ASTM standard methods. SCC performed well relative to conventional concrete at high strengths, but not as well at normal strengths for shrinkage and creep. HVFA, however, outperformed conventional concrete in both shrinkage and creep. Abrasion resistance was primarily dependant on concrete strength, not concrete type.

ACKNOWLEDGEMENTS

I would like to thank my advisor, Dr. John J. Myers, for the opportunity to pursue research and his guidance throughout the project. Furthermore, I would like to thank my committee members, Dr. Jeffery S. Volz and Dr. David N. Richardson for their additional guidance and support.

I would like to thank the Missouri Department of Transportation (MoDOT) and the NUTC Center for Infrastructure and Safety for sponsoring the project. I would also like to thank the Center for Infrastructure Engineering Studies (CIES) and the Department of Civil, Architectural, and Environmental Engineering (CArEE) for providing additional support throughout the project.

Thank you to the staff and technicians of CIES and CArEE who helped throughout the project, especially Jason Cox, John Bullock, Gary Abbott, and Scott Parker.

Additionally, I would like to thank the members of my project team, Kyle Holman, Eric Sells, Trevor Looney, Krista Porterfield, and Mahdi Arezoumandi for their tremendous work done throughout this project.

Finally, I would like to thank my family, particularly my Mom and sister, and friends who have supported me throughout my education.

This thesis is dedicated to my father, Tim Tucker.

TABLE OF CONTENTS

	Page
ABSTRACT	iii
ACKNOWLEDGEMENTS.....	iv
LIST OF ILLUSTRATIONS.....	ix
LIST OF TABLES.....	xii
NOMENCLATURE	xiii
 SECTION	
1. INTRODUCTION.....	1
1.1. BACKGROUND	1
1.2. OBJECTIVES.....	1
1.3. SCOPE	2
1.4. ORGANIZATION OF REPORT.....	2
2. LITERATURE REVIEW	3
2.1. SELF-CONSOLIDATING CONCRETE (SCC).....	3
2.1.1. Definition of SCC.....	3
2.1.2. Advantages of SCC	3
2.2. HIGH VOLUME FLY ASH CONCRETE (HVFA)	3
2.2.1. Fly Ash.....	3
2.2.2. Definition of HFVA	4
2.2.3. Advantages of HVFA.....	4
2.3. SHRINKAGE OF CONCRETE	5
2.3.1. Definition of Shrinkage	5
2.3.2. Factors Affecting Shrinkage.....	6
2.4. SHRINKAGE MODELS.....	8
2.4.1. ACI 209R-92	8
2.4.2. NCHRP Report 496 (2003)	11
2.4.3. Model B3.....	13

2.4.4. CEB-FIP 90	14
2.4.5. GL 2000.....	16
2.5. SCC SHRINKAGE RESEARCH.....	17
2.5.1. NCHRP Report 628 (2009)	17
2.5.2. Shindler, et. al.....	18
2.5.3. Fernandez-Gomez and Landsberger.....	18
2.5.4. Long, et. al.....	18
2.6. HVFA SHRINKAGE RESEARCH.....	19
2.6.1. Atis... ..	20
2.6.2. Termkhajornkit, et. al.	21
2.6.3. Gao, et. al.....	21
2.6.4. Nath and Sarker	22
2.7. CREEP OF CONCRETE.....	23
2.7.1. Definition of Creep.....	23
2.7.2. Factors Affecting Creep	24
2.8. CREEP MODELS.....	25
2.8.1. ACI 209R-92	25
2.8.2. NCHRP Report 496.....	27
2.8.3. CEB-FIP 90	28
2.8.4. GL 2000.....	29
2.9. SCC CREEP RESEARCH.....	29
2.9.1. NCHRP Report 628.....	29
2.9.2. Long and Khayat	30
2.9.3. Long, et. el.....	31
2.10. HVFA CREEP RESEARCH	31
2.10.1. ACI 232.2R-03	31
2.10.2. Alexander, et. al.....	31
2.11. Application of Shrinkage and Creep.....	32
2.11.1. Prestress Loss	32
2.11.2. Load Effects	33
2.11.3. Beam Deflection.....	34

2.12. CONCRETE ABRASION	34
2.12.1. Definition of Concrete Abrasion	34
2.12.2. Factors Affecting Concrete Abrasion.....	34
2.13. SCC ABRASION RESEARCH.....	35
2.14. HVFA ABRASION RESEARCH	35
2.14.1. Naik, et. al.	35
2.14.2. Atis.	36
3. RESEARCH PROGRAM	37
3.1. MIX DESIGNS	37
3.1.1. SCC..	37
3.1.2. HVFA	38
3.2. SHRINKAGE AND CREEP SPECIMEN CONSTRUCTION.....	39
3.2.1. Shrinkage and Creep Specimens	39
3.2.2. Shrinkage and Creep Molds	39
3.2.3. Shrinkage and Creep Specimen Casting	40
3.2.4. Shrinkage and Creep De-Molding and Preparation	41
3.2.5. Shrinkage and Creep Data Acquisition	41
3.3. ABRASION SPECIMEN CONSTRUCTION	42
3.4. TESTING PROCEDURES.....	43
3.4.1. Shrinkage Testing Procedures	43
3.4.2. Creep Testing Procedures.....	46
3.4.3. Abrasion Resistance Testing Procedures	49
4. SCC RESULTS AND DISCUSSION	53
4.1. SHRINKAGE	53
4.1.1. Results	53
4.1.2. Discussion and Conclusions.....	53
4.2. CREEP	61
4.2.1. Results	61
4.2.2. Discussion and Conclusions.....	62
4.3. ABRASION RESISTANCE.....	66
4.3.1. Results	66

4.3.2. Discussion and Conclusions	69
5. HVFA RESULTS AND DISCUSSION.....	71
5.1. SHRINKAGE	71
5.1.1. Results	71
5.1.2. Discussion and Conclusions.....	71
5.2. CREEP	79
5.2.1. Results.	79
5.2.2. Discussion and Conclusions.....	79
5.3. ABRASION RESISTANCE.....	80
5.3.1. Results	80
5.3.2. Discussion and Conclusions.....	84
APPENDICES	
A. SHRINKAGE WITH RELATIVE HUMIDITY DATA.....	86
B. EXAMPLE STRAIN CALCULATIONS	94
C. COEFFICIENT OF VARIATION DATA	97
BIBLIOGRAPHY.....	102
VITA.....	105

LIST OF ILLUSTRATIONS

	Page
Figure 2.1 - Relationship Between Moist Cure Time and Shrinkage Strain	7
Figure 2.2 - Series A Shrinkage Results (adapted from Nath and Sarker)	22
Figure 2.3 - Series B Shrinkage Results (adapted from Nath and Sarker)	23
Figure 2.4 - Stress vs. Time for Prestressed Bridge Girder (Tadros et. al. 2003).....	33
Figure 3.1 - Shrinkage and Creep Form.....	40
Figure 3.2 – Shrinkage and Creep Specimens and DEMEC Point Arrangement (Myers and Yang, 2005)	42
Figure 3.3 – DEMEC Reading Taken on Specimen	44
Figure 3.4 - Reference Bar	44
Figure 3.5 - Reading Taken on Reference Bar	45
Figure 3.6 - Gauge Factor Used for Shrinkage and Creep Calculations.....	45
Figure 3.7 - Example DEMEC Gauge Reading.....	45
Figure 3.8 - Schematic of Creep Loading Frame (Myers and Yang, 2005)	46
Figure 3.9 - Creep Loading Frame with Specimen.....	47
Figure 3.10 - Reading Taken on Creep Specimen	48
Figure 3.11 - Schematic of Abrasion Rotating Cutter (ASTM C944).....	50
Figure 3.12 - Rotating Cutter	50
Figure 3.13 - Abrasion Resistance Test In Progress	51
Figure 3.14 - Depth of Wear Measurement Points	51
Figure 3.15 - Abrasion Resistance Specimen After Testing.....	52
Figure 4.1 - C6-58L Shrinkage Results and Prediction Models	55

Figure 4.2 - S6-48L Shrinkage Results and Prediction Models.....	56
Figure 4.3 - C10-58L Shrinkage Results and Prediction Models	57
Figure 4.4 - S10-58L Shrinkage Results and Prediction Models.....	58
Figure 4.5 - SCC Shrinkage Results (Best fit Logarithmic)	59
Figure 4.6 – SCC Results with Shrinkage Databases (Fernandez-Gomez, Shindler et. al., and Holshemacher)	60
Figure 4.7 – SCC Coefficient of Creep Results	63
Figure 4.8 – S6-48L Plotted Against Results from Long and Khayat (2011)	64
Figure 4.9 – S10-48L Plotted Against Results from Long and Khayat (2011)	65
Figure 4.10 - C6-58L Mass Loss Results.....	66
Figure 4.11 - S6-48L Mass Loss Results	67
Figure 4.12 - C10-58L Mass Loss Results.....	67
Figure 4.13 - S10-48L Mass Loss Results	68
Figure 4.14 - SCC Mass Loss Results	68
Figure 4.15 - SCC Depth of Wear Results.....	69
Figure 5.1 - HVFA-C Shrinkage Results and Prediction Models.....	72
Figure 5.2 - HVFA-H Shrinkage Results and Prediction Models	73
Figure 5.3 - HVFA-L Shrinkage Results and Prediction Models.....	74
Figure 5.4 – HVFA Shrinkage Results (Best fit Logarithmic)	75
Figure 5.5 – HVFA Shrinkage Results Compared to Marlay (2011)	76
Figure 5.6 – HVFA Shrinkage Results Compared to Atis (2003)	77
Figure 5.7 – HVFA Results with Shrinkage Databases	78
Figure 5.8 - HVFA-C Mass Loss Results	81
Figure 5.9 - HVFA-H Mass Loss Results	81

Figure 5.10 - HVFA-L Mass Loss Results 82

Figure 5.11 - HVFA Average Depth of Wear by Age 82

Figure 5.12 - HVFA Average Mass Loss by Age..... 83

Figure 5.13 - HVFA Mass Loss Results 83

Figure 5.14 - HVFA Depth of Wear Results 84

LIST OF TABLES

	Page
Table 2.1 - Standard Conditions as Defined by ACI 209R-92	9
Table 2.2 – Coded Values for Eqs. 2.48 – 2.49	19
Table 2.3 - Mix Designs (Atis 2003) (kg per cubic meter).....	20
Table 2.4 - Experimental Shrinkage Results (Atis 2003) (microstrain)	21
Table 3.1 - SCC Test Program Mix Designs and Mechanical Properties.....	38
Table 3.2 - HVFA Test Program Mix Designs and Mechanical Properties	39
Table 4.1 – SCC Results Compared to Eqs. 2.48 – 2.49 by Long et. al.	61
Table 4.2 - Summary of SCC Creep Results	61
Table 4.3 - Summary of Results Shown with 28 Day Measured Compressive Strength	69
Table 5.1 - Summary of HVFA Creep Results	79
Table 5.2 - Average Mass Loss Shown with 28 Day Compressive Strength	84

NOMENCLATURE

Symbol	Description
A	Cement type correction factor (NCHRP 628)
A_c	Cross-section area (mm^2) (CEB-FIP 90)
c	Cement content (lb/yd^3) (ACI 209R-92)
D	Effective cross-section thickness (Model B3)
D_0	Datum reading on the reference bar
D_i	Subsequent reading on the reference bar
f	Size effects factor (ACI 209R-92)
f'_c	Tested compressive strength of concrete (psi, ksi, MPa)
f'_{ci}	Specified compressive strength of concrete (ksi) (NCHRP 496)
f_{cm}	Tested compressive strength of concrete at 28 days age (psi, ksi, MPa) (CEB-FIP 90)
G	Gauge factor
H	Relative humidity (% or decimal)
K	Cement type correction factor (GL 2000)
k_f	Concrete strength factor (NCHRP 496)
k_{hc}	Humidity factor (NCHRP 496)
k_{hs}	Humidity factor (NCHRP 496 and NCHRP 628)
k_{la}	Loading factor (NCHRP 496)
k_s	Size factor (NCHRP 496 and NCHRP 628) or Cross-section shape factor (Model B3)
k_{td}	Time development factor (NCHRP 496)

R_0	Datum reading on tested material
RH	Relative humidity (%) (CEB-FIP 90)
R_i	Subsequent reading on tested material
s	Slump of fresh concrete (in)
S(t)	Time dependence factor (Model B3)
t	Age of concrete (days)
t_0	Age of concrete when drying begins (days) (Model B3) or Age at which creep specimen is loaded (days) (ACI 209R-92 and CEB FIP 90)
t_c	Age of concrete when drying begins (days) (ACI 209R-92 and GL 2000)
t_i	Age at which creep specimen is loaded (days) (NCHRP 496)
t_s	Age of concrete at the beginning of shrinkage (days) (CEB-FIP 90)
u	Perimeter in contact with the atmosphere (mm) (CEB-FIP 90)
V/S	Volume to Surface area ratio (in or mm)
w	Water content of concrete (lb/ft ³)
α	Concrete air content (%)
α_1	Cement type correction factor (Model B3)
α_2	Curing condition correction factor
$\beta(h)$	Humidity correction factor (GL 2000)
$\beta(t)$	Time effect correction factor (GL 2000)
β_c	Coefficient to describe the development of creep with time after loading (CEB FIP 90)

β_{RH}	Relative humidity correction factor (CEB-FIP 90)
β_s	Coefficient to describe the development of shrinkage with time (CEB-FIP 90)
β_{sc}	Concrete type correction factor (CEB-FIP 90)
$\gamma_{c,RH}$	Humidity correction factor (ACI 209R-92)
$\gamma_{c,s}$	Slump correction factor (ACI 209R-92)
$\gamma_{c,t0}$	Curing condition correction factor (ACI 209R-92)
$\gamma_{c,vs}$	Size correction factor (ACI 209R-92)
$\gamma_{c,\alpha}$	Air content correction factor (ACI 209R-92)
$\gamma_{c,\psi}$	Fine aggregate correction factor (ACI 209R-92)
$\gamma_{sh,c}$	Cement content correction factor (ACI 209R-92)
$\gamma_{sh,RH}$	Relative humidity correction factor (ACI 209R-92)
$\gamma_{sh,s}$	Slump correction factor (ACI 209R-92)
$\gamma_{sh,tc}$	Initial moist cure duration correction factor (ACI 209R-92)
$\gamma_{sh,vs}$	Volume/surface area correction factor (ACI 209R-92)
$\gamma_{sh,\alpha}$	Air content correction factor (ACI 209R-92)
$\gamma_{sh,\psi}$	Fine aggregate correction factor (ACI 209R-92)
Δ_{ϵ_c}	Change in creep strain from one reading to the next
Δ_{ϵ_s}	Change in shrinkage strain from one reading to the next
ϵ_{cso}	Notional shrinkage coefficient (CEB-FIP 90)
$\epsilon_{es(t,ts)}$	Calculated ultimate shrinkage strain ($\mu\epsilon$) (CEB-FIP 90)
ϵ_i	Measured strain due to initial loading of creep specimen
$\epsilon_{es(t,t0)}$	Calculated shrinkage strain at a given age ($\mu\epsilon$) (Model B3)

ϵ_{sh}	Calculated shrinkage strain at a given age ($\mu\epsilon$) (NCHRP 496, GL 2000, and NCHRP 628)
$\epsilon_{sh(t,tc)}$	Calculated shrinkage strain at a given age ($\mu\epsilon$) (ACI 209R-92)
ϵ_{shu}	Calculated ultimate shrinkage strain ($\mu\epsilon$) (ACI 209R-92) or Notional ultimate shrinkage strain (GL 2000)
$\epsilon_{sh\infty}$	Calculated ultimate shrinkage strain ($\mu\epsilon$) (Model B3)
ϵ_t	Measured creep strain at a given age
λ_{Δ}	Multiplier for additional deflection due to long-term effects (ACI 318-08)
ξ	Time dependant factor for sustained load (ACI 318-08)
ρ'	Compression reinforcement ratio (ACI 318-08)
τ_{sh}	Size dependence factor (Model B3)
$\Phi_{(t,t_0)}$	Calculated creep coefficient at a given age (ACI 209R-92 and CEB FIP 90) or Measured creep coefficient at a given age
Φ_0	Notional creep coefficient (CEB FIP 90)
Φ_{28}	Calculated creep coefficient at a given age (GL 2000)
$\Phi_{(tc)}$	Factor that takes into account drying before loading (GL 2000)
Φ_u	Calculated ultimate creep coefficient (ACI 209R-92)
Ψ	Ratio of fine aggregate to total aggregate by weight (%)
$\Psi_{(t,t_i)}$	Calculated creep coefficient at a given age (NCHRP 496 and NCHRP 628)

1. INTRODUCTION

1.1. BACKGROUND

Over time, concrete as a construction material has advanced significantly, from primitive clay structures to the development of hydraulic cement and on to the invention of reinforced concrete. Even with this advancement, concrete as a building material can be further improved with the use of certain admixtures or the addition of different materials so that new variations of concrete can be made which may offer benefits over traditional concrete for certain applications. These new variations on concrete, including self consolidating concrete (SCC) and high volume fly ash concrete (HVFA), have been developed to not only increase the structural capabilities of concrete, but to also address the growing desire for sustainable building materials.

With the development of these new types of concrete, it is important to understand the behavior of the material in order to design and build adequate and safe structures. Understanding the shrinkage and creep behavior of SCC and HVFA is important because of their effect on prestress loss, load determination, and serviceability of structural members. Additionally, understanding the material's susceptibility to abrasion is important in determining the materials adequacy for use in abrasive environments, such as exposure to weathering or tire friction in the case of concrete used in the construction of a bridge sub-structure, super-structure, or deck.

1.2. OBJECTIVES

The objectives of this study are to evaluate the adequacy of SCC and HVFA for use in transportation infrastructure. This is achieved by relating data obtained by testing

SCC and HVFA to that of conventional concrete. Further, the data will be compared to theoretical values calculated using various prediction models.

1.3. SCOPE

In this study, specimens were fabricated for testing of shrinkage, creep, and abrasion resistance. Measurements on shrinkage specimens were made for a minimum of 154 days after demolding and measurements on creep specimens for a minimum of 126 days after loading. Abrasion specimens were tested at 28 days age for both SCC and HVFA and again at 70 days age for HVFA specimens only.

1.4. ORGANIZATION OF REPORT

This report is organized into 5 sections. It starts with an introduction to the testing program, including background on why the research is necessary, the goals of the program, and the scope. Section 2 contains a comprehensive review of shrinkage and creep prediction models, as well as similar studies done in the past relating to shrinkage, creep, or abrasion resistance of SCC and HVFA. Section 3 contains details on the testing program, including mix designs used and procedures for specimen construction and testing. Sections 4 and 5 contain results and conclusions for SCC and HVFA, respectively.

2. LITERATURE REVIEW

2.1. SELF-CONSOLIDATING CONCRETE (SCC)

2.1.1. Definition of SCC. ACI 237R-07 defines self-consolidating concrete as “highly flowable, nonsegregating concrete that can spread into place, fill the formwork, and encapsulate the reinforcement without any mechanical consolidation.” In order to achieve the necessary fluidity, a high range water reducer (HRWR) is often utilized.

2.1.2. Advantages of SCC. The choice of SCC over conventional concrete results in both economical and material performance benefits. The use of SCC eliminates the necessity of manual compaction, typically achieved by vibration. The self-leveling properties of SCC additionally reduce or eliminate the need for screeding operations to achieve a flat surface. This reduction in jobsite labor and equipment forces, along with the time saved by not having to perform these labor intensive operations, lead to significant savings. Because of its fluidity, SCC has the ability to effectively flow into areas that conventional concrete cannot. SCC is therefore ideal for construction of members with significant reinforcement congestion or unusually shaped members. This allows for greater freedom in member design and reinforcement detailing. Finally, the reduction in honeycombing is beneficial both structurally and aesthetically (ACI 237R-07).

2.2. HIGH VOLUME FLY ASH CONCRETE (HVFA)

2.2.1. Fly Ash. Fly ash is defined by ACI 116R-00 as “the finely divided residue that results from the combustion of ground or powdered coal and that is transported by flue gases from the combustion zone to the particle removal system.” Fly ash is often

collected in this manner from coal burning electric power plants and is considered a waste product of the power plant. As reported by the American Coal Ash Association's 2010 Coal Combustion Product Production & Use Survey Report, there were 67,700,000 tons (61,400,000,000 kg) of fly ash produced, of which 11,000,000 tons (9,990,000,000 kg) (16.3%) were used in concrete, concrete products, or grout.

2.2.2. Definition of HFVA. Concretes containing 15% - 35% fly ash replacement by mass of total cementitious material are typically used. High volume concrete is concrete that contains a much higher percentage of fly ash replacement than the typical fly ash concrete mix. The exact definition of high volume fly ash concrete varies depending on the source. ACI 232.2R-03 states "HVFA concrete may be defined as having a fly ash content of 50% or greater by mass of cementitious materials." ACI also cites research from Haque, Langan, and Ward (1984) and Ramme and Tharaniyil (2000) which define high volume fly ash concrete as concrete with fly ash replacement of 40% and 37% respectively. The report concludes that "HVFA concrete can be considered to represent concrete containing higher percentages of fly ash than normal for the intended application of the concrete." (ACI 232.2R-11)

2.2.3. Advantages of HVFA. The advantages of using fly ash as a replacement for Portland cement in concrete production include economic benefits, environmental benefits, as well as some advantageous material properties. Fly ash is generally cheaper to purchase than Portland cement, however this is dependent on local availability and transportation costs. Since fly ash is otherwise considered a waste product, which is either disposed of in landfills or released into the atmosphere, its use as a recycled material is considered very environmentally advantageous. The use of HVFA can

contribute to LEED certification by the U.S. Green Building Council, applicable to MR credit 4-recycled content. (USGBC) Use of fly ash also has beneficial effects on the properties of the concrete in which it is used. Because fly ash has a lower specific gravity than cement, its replacement by mass will increase the paste volume of the concrete, allowing for an increase in workability. Fly ash also contributes to less bleeding in fresh concrete. HVFA also retards setting time and strength gain, which can be beneficial in mass concrete projects. Research has also shown that fly ash concrete reaches a higher ultimate strength than conventional concrete.

2.3. SHRINKAGE OF CONCRETE

2.3.1. Definition of Shrinkage. Shrinkage of concrete is the decrease in volume of hardened concrete with time. Shrinkage is expressed as the strain measured on a load-free specimen, most often as the dimensionless unit microstrain (strain $\times 10^{-6}$). Concrete experiences shrinkage in three ways, drying shrinkage, autogenous (chemical) shrinkage, and carbonation shrinkage. Autogenous shrinkage is due strictly to the hydration reactions of the cement. Drying shrinkage is the strain imposed on a specimen exposed to the atmosphere and allowed to dry. Carbonation shrinkage is caused by the reaction of calcium hydroxide with cement with carbon dioxide in the atmosphere. The magnitude and rate of shrinkage is dependent on a number of factors. These factors are accounted for and described in the various industry models and research projects in the following sections.

2.3.2. Factors Affecting Shrinkage (ACI 209.1R-05). Shrinkage of concrete is closely related to shrinkage of paste. Therefore the amount of paste in the mix significantly affects the level of concrete shrinkage. Paste volume is determined by the quantity, size, and gradation of aggregate. Because paste volume is largely dependent on aggregate properties, the most important factor in determining a concrete's shrinkage level is the aggregate used in the mix. Similarly, the water content, cement content, and slump will affect the shrinkage of concrete. These three factors are indications of the paste volume and therefore can be used to determine the shrinkage potential of a mix. Aggregate acts as a restraining force to shrinkage, therefore an aggregate with a higher modulus of elasticity (MOE) will better restrain against shrinkage than an aggregate with a lower MOE. The characteristics of the cement itself are other significant indicators of shrinkage potential. Research has shown cements with low sulfate content, high alumina content, and cements that are finely ground exhibit increased shrinkage.

The environment which the concrete is exposed to can also influence shrinkage. The biggest environmental factor is the relative humidity of the surrounding air. As shown by **Eq. 2.1**, as relative humidity increases, shrinkage decreases due to the decrease in potential moisture loss. It has also been shown that an increase in temperature increases the ultimate shrinkage of concrete.

$$\text{shrinkage} \propto 1 - \left(\frac{h}{100}\right)^b \quad (2.1)$$

Where: h is relative humidity in percent, and b is a constant that ranges from 1 to 4.

Finally, the design and construction of concrete specimens can influence shrinkage. The curing conditions experienced by the concrete have a significant effect on shrinkage.

Generally, the longer the specimen is allowed to moist cure, the less it will shrink.

However, research conducted by Perenchio (1997), **Figure 2.1**, shows that there may not be a simple relationship between moist cure time and shrinkage.




Figure 2.1 - Relationship Between Moist Cure Time and Shrinkage Strain
(adapted from Perenchio 1997)

Larger members tend to dry slower, so the ratio of volume to surface area is a significant factor in shrinkage of concrete.

$$\text{shrinkage} \propto \frac{1}{\left(\frac{V}{S}\right)^2} \quad (2.2)$$

Where: V/S is the volume to surface area ratio in inches.

2.4. SHRINKAGE MODELS.

The ability to accurately predict the shrinkage of a concrete structure is extremely important. An accurate model for shrinkage will allow the engineer to predict long term serviceability, durability, and stability of a given structure. As mentioned above, there are many different factors that affect a concrete's susceptibility to shrinkage. Because of these factors, accurate prediction of shrinkage is very difficult. The models described below take into account many of the factors described above in their attempt to predict concrete shrinkage (Bazant and Baweja, 2000).

2.4.1. ACI 209R-92. This model, developed by Branson and Christiason (1971) and modified by ACI committee 209, predicts shrinkage strain of concrete at a given age under standard conditions. The original model by Branson and Christiason was developed based on a best fit from a sample of 95 shrinkage specimens and using an ultimate shrinkage strain of 800×10^{-6} in./in. (mm/mm). However, subsequent research by Branson and Chen, based on a sample of 356 shrinkage data points, concluded that the ultimate shrinkage strain should be 780×10^{-6} in./in. (mm/mm). The prediction model, **Eq. 2.3 – 2.5**, apply only to the standard conditions as shown in **Table 2.1**.

$$\epsilon_{sh}(t, t_c) = \frac{(t-t_c)^\alpha}{f+(t-t_c)^\alpha} \epsilon_{shu} \quad (\mu\epsilon) \quad (2.3)$$

$$\epsilon_{shu} = 780 \times 10^{-6} \quad (\mu\epsilon) \quad (2.4)$$

$$f = 26.0e^{\{0.36(V/S)\}} \quad (2.5)$$

Where: f is 35 (moist cure) or 55 (steam cure), or by **Eq. 2.5** if size effects are to be considered, α is assumed to be 1, t is the age of concrete in days, and t_c is the age of concrete when drying begins in days.

Table 2.1 - Standard Conditions as Defined by ACI 209R-92

Factors		Variables		Standard
Concrete	Concrete Composition	Cement Paste Content	Type of Cement	Type I or III
		W/C	Slump	2.7 in (70mm)
		Mix Proportions	Air Content	$\leq 6\%$
		Aggregate Characteristics	Fine Aggregate %	50%
		Degree of Compaction	Cement Content	470 to 752 lb/yd ³ (279 to 446 kg/m ³)
	Initial Curing	Length of Initial Curing	Moist Cured	7 days
			Steam Cured	1 - 3 days
		Curing Temperature	Moist Cured	73.4 \pm 4°F (23 \pm 2°C)
			Steam Cured	$\leq 212^\circ\text{F}$ ($\leq 100^\circ\text{C}$)
	Curing Humidity	Relative Humidity	$\geq 95\%$	
Member Geometry & Environment	Environment	Concrete Temperature	Concrete Temperature	73.4°F \pm 4°F (23 \pm 2°C)
		Concrete Water Content	Ambient Relative Humidity	40%
	Geometry	Size and Shape	Volume-Surface Ratio (V/S)	V/S = 1.5 in (38mm)
			Minimum Thickness	6 in (150mm)

When concrete is not subject to any or all of the standard conditions, correction factors shall be applied, as shown in **Eq. 2.6 – 2.16**.

$$\varepsilon_{sh}(t, t_c) = \frac{(t-t_c)^\alpha}{f+(t-t_c)^\alpha} \times \varepsilon_{shu} \quad (\mu\varepsilon) \quad (2.6)$$

$$f = 26.0e^{0.36(V/S)} \quad (2.7)$$

$$\varepsilon_{shu} = 780\gamma_{sh} \times 10^{-6} \quad (\mu\varepsilon) \quad (2.8)$$

$$\gamma_{sh} = \gamma_{sh,tc} \gamma_{sh,RH} \gamma_{sh,vs} \gamma_{sh,s} \gamma_{sh,\psi} \gamma_{sh,c} \gamma_{sh,\alpha} \quad (2.9)$$

$$\gamma_{sh,tc} = 1.202 - .2337 \log(t_c) \quad (2.10)$$

$$\gamma_{sh,RH} = \begin{cases} 1.40 - 1.02h & \text{for } 0.40 \leq h \leq 0.80 \\ 3.00 - 3.0h & \text{for } 0.80 \leq h \leq 1 \end{cases} \quad (2.11)$$

$$\gamma_{sh,vs} = 1.2e^{-0.12(V/S)} \quad (2.12)$$

$$\gamma_{sh,s} = 0.89 + 0.041s \quad (2.13)$$

$$\gamma_{sh,\psi} = \begin{cases} 0.30 + 0.014\psi & \text{for } \psi \leq 50\% \\ 0.90 + 0.002\psi & \text{for } \psi > 50\% \end{cases} \quad (2.14)$$

$$\gamma_{sh,c} = 0.75 + 0.00036c \quad (2.15)$$

$$\gamma_{sh,\alpha} = 0.95 + 0.008\alpha \geq 1 \quad (2.16)$$

Where: $\epsilon_{sh}(t,t_c)$ is the calculated shrinkage strain at a given age, ϵ_{shu} is the calculated ultimate shrinkage strain, γ_{sh,t_c} is the initial moist cure duration correction factor, t is the age of concrete in days, t_c is the age of concrete when drying starts in days, $\gamma_{sh,RH}$ is the relative humidity correction factor, h is humidity in decimals, $\gamma_{sh,vs}$ is the volume/surface area correction factor, where V/S is the volume to surface area ratio in inches, $\gamma_{sh,s}$ is the slump correction factor, s is slump in inches, $\gamma_{sh,\psi}$ is the fine aggregate correction factor, ψ is the ratio of fine aggregate to total aggregate by weight expressed as percentage, $\gamma_{sh,c}$ is the cement content correction factor, c is the cement content in lb/yd^3 , $\gamma_{sh,\alpha}$ is the air content correction factor, and α is the air content in percent. In **Eq 2.6**, the value of α can be assumed to be equal to 1, with f assumed to be equal to 35 for concrete that is moist cured for seven days or 55 for concrete subject to 1-3 days of steam curing. In order to totally consider shape and size effects, α is still assumed to be equal to 1, with f given by **Eq. 2.7**.

2.4.2. NCHRP Report 496 (2003). The National Cooperative Highway Research Program (NCHRP) conducted research on shrinkage of high strength concrete in the states of Nebraska, New Hampshire, Texas, and Washington. This research project was sponsored by the American Association of State Highway and Transportation Officials (AASHTO) and the results adopted into the 2007 AASHTO LRFD Bridge Design Specifications. Laboratory shrinkage data was obtained from three 4 in. (101.6 mm) by 4 in. (101.6 mm) by 24 in. (609.6 mm) specimens per mix, with a total of 48 specimens tested including both normal and high strength concrete. Field specimens were also made and cured in the same condition as corresponding bridge girders in each of the four participating states. The field program consisted of a set of three 4 in. (101.6 mm) by 4

in. (101.6 mm) by 24 in. (609.6 mm) shrinkage specimens at each location with measurements taken for 3 months. The data showed that an ultimate shrinkage strain of 480×10^{-6} in./in. (mm/mm) should be assumed. The modification factors in the model account for the effects of high strength concrete. **Eq. 2.17 – 2.22** present the proposed shrinkage formula as proposed in this study.

$$\epsilon_{sh} = 480 \times 10^{-6} \gamma_{sh} \quad (\mu\epsilon) \quad (2.17)$$

$$\gamma_{sh} = k_{td} k_s k_{hs} k_f \quad (2.18)$$

$$k_{td} = \frac{t}{61 - 4f'_{ci} + t} \quad (2.19)$$

$$k_{hs} = 2.00 - 0.0143H \quad (2.20)$$

$$k_s = \frac{1064 - 94V/S}{735} \quad (2.21)$$

$$k_f = \frac{5}{1 + f'_{ci}} \quad (2.22)$$

Where: ϵ_{sh} is the calculated shrinkage strain at a given age, k_{td} is the time development factor, t is the age of the concrete in days, k_{hs} is the humidity factor, H is the average ambient relative humidity in percent, k_s is the size factor, V/S is the volume to surface

area ratio in inches, k_f is the concrete strength factor, and f'_{ci} is the specified compressive strength of concrete in ksi.

2.4.3. Model B3. Model B3 (Bazant and Baweja) is the third update of shrinkage predictions developed at Northwestern University, based on BP model β_3 and BP-KX model β_4 . This model is simpler than previous versions and is validated by a larger set of test data. **Eq. 2.23 – 2.32** present the B3 shrinkage prediction model.

$$\varepsilon_{sh}(t, t_0) = -\varepsilon_{sh\infty} k_h S(t) \quad (\mu\varepsilon) \quad (2.23)$$

$$S(t) = \tanh \sqrt{\frac{t-t_0}{\tau_{sh}}} \quad (2.24)$$

$$k_h = \begin{cases} 1 - h^3 & \text{for } h \leq 0.98 \\ -0.2 & \text{for } h = 1 \text{ (swelling in water)} \\ \text{linear} & \\ \text{interpolation} & \text{for } 0.98 \leq h \leq 1 \end{cases} \quad (2.25)$$

$$\tau_{sh} = k_t (k_s D)^2 \quad (2.26)$$

$$k_t = 190.8 t_0^{-0.08} f'_c{}^{-1/4} \quad (2.27)$$

$$D = \sqrt[2]{V/S} \text{ (in.)} \quad (2.28)$$

$$k_s = \begin{array}{ll} 1.00 & \text{for an infinite slab} \\ 1.15 & \text{for an infinite cylinder} \\ 1.25 & \text{for an infinite square prism} \\ 1.30 & \text{for a sphere} \\ 1.55 & \text{for a cube} \end{array} \quad (2.29)$$

$$\varepsilon_{sh\infty} = -\alpha_1 \alpha_2 [26w^{2.1} f'_c{}^{-0.28} + 270] \quad (\mu\varepsilon) \quad (2.30)$$

$$\alpha_1 = \begin{array}{ll} 1.0 & \text{for type I cement} \\ 0.85 & \text{for type II cement} \\ 1.1 & \text{for type III cement} \end{array} \quad (2.31)$$

$$\alpha_2 = \begin{array}{ll} 0.75 & \text{for steam – curing} \\ 1.2 & \text{for sealed or normal curing in air} \\ & \text{with initial protection against drying} \\ 1.0 & \text{for curing in water or at 100\% relative humidity} \end{array} \quad (2.32)$$

Where: $\varepsilon_{shu}(t, t_0)$ is the calculated shrinkage strain at a given age, $S(t)$ is the time dependence factor, t is the age of concrete in days, t_0 is the age of concrete at which drying begins, τ_{sh} is the size dependence factor, f'_c is the cylinder compressive strength in psi, D is the effective cross-section thickness, V/S is the volume to surface area ratio in inches, k_s is the cross-section shape factor, $\varepsilon_{sh\infty}$ is the calculated ultimate shrinkage strain, α_1 is the cement type correction factor, α_2 is the curing condition correction factor, and w is the water content of the concrete in lb/ft^3 .

2.4.4. CEB-FIP 90. This model, developed jointly by Euro-International Concrete Committee (CEB – Comité Euro-International du Béton) and the International Federation for Prestressing (FIP – Fédération Internationale de la Précontrainte) is found in the CEB-FIP Model Code 1990. It is stated that due to its international character, the

code is more general than most and does not apply to any particular structure type. **Eq. 2.33 – 2.38** present this model for calculating shrinkage strain.

$$\varepsilon_{es}(t, t_s) = \varepsilon_{cso} \beta_s (t - t_s) \quad (\mu\varepsilon) \quad (2.33)$$

$$\varepsilon_{cso} = \varepsilon_s(f_{cm})(\beta_{RH}) \quad (2.34)$$

$$\beta_s(t - t_s) = \sqrt{\frac{(t - t_s)}{350 \left(\frac{2A_c}{100u} \right)^2 + (t - t_s)}} \quad (2.35)$$

$$\varepsilon_s(f_{cm}) = [160 + 10\beta_{sc}(9 - 0.1f_{cm})] \times 10^{-6} \quad (2.36)$$

$$\beta_{RH} = -1.55 \left[1 - \left(\frac{RH}{100} \right)^3 \right] \quad (2.37)$$

$$\beta_{sc} = \begin{cases} 4 & \text{for slowly hardening cements} \\ 5 & \text{for normal or rapid hardening cements} \\ 8 & \text{for rapid hardening high strength cements} \end{cases} \quad (2.38)$$

Where: $\varepsilon_{es}(t, t_s)$ is the calculated ultimate shrinkage strain, ε_{cso} is the notional shrinkage coefficient, β_s is the coefficient to describe the development of shrinkage with time, t is the age of concrete in days, t_s is the age of concrete at the beginning of shrinkage in days, A_c is the cross section area in mm^2 , u is the perimeter in contact with the atmosphere in mm, f_{cm} is the compressive strength of concrete at age of 28 days in MPa, β_{RH} is the relative humidity correction factor, RH is the relative humidity in percent, and β_{sc} is the concrete type correction factor.

2.4.5. GL 2000. This model, developed by Gardener and Lockman was published in the ACI materials journal under the title “Design provisions for drying shrinkage and Creep of Normal-Strength Concrete.” The model developed is shown in **Eq. 2.39 – 2.43.**

$$\varepsilon_{sh} = \varepsilon_{shu}\beta(h)\beta(t) \quad (\mu\varepsilon) \quad (2.39)$$

$$\varepsilon_{shu} = 1000K\sqrt{\frac{30}{f'_c}} \times 10^{-6} \quad (\mu\varepsilon) \quad (2.40)$$

$$\beta(h) = 1 - 1.18h^4 \quad (2.41)$$

$$\beta(t) = \sqrt{\frac{t-t_c}{t-t_c+0.15(V/S)^2}} \quad (2.42)$$

$$K = \begin{array}{ll} 1 & \text{for type I cement} \\ 0.75 & \text{for type II cement} \\ 1.15 & \text{for type III cement} \end{array} \quad (2.43)$$

Where: ε_{sh} is the calculated shrinkage strain at a given age, ε_{shu} is the notional ultimate shrinkage strain, $\beta(h)$ is the humidity correction factor, h is humidity in decimals, $\beta(t)$ is the correction factor for the effect of time on shrinkage, t_c is the age that drying has commenced in days, t is age of concrete in days, V/S is the volume to surface area ratio, and K is the cement type correction factor.

2.5. SCC SHRINKAGE RESEARCH

A number of shrinkage models have been developed which are formulated specifically for self consolidating concrete. The sections to follow present some shrinkage models that apply to SCC.

2.5.1. NCHRP Report 628 (2009). The study undertaken as part of NCHRP Report 628 concluded that the most accurate current prediction model for shrinkage of SCC was the CEB-FIP 90 at the time of investigation. In addition to this, there is also a proposed model for shrinkage of SCC. This model, shown in **Eq. 2.44 – 2.47** is simply the AASHTO 2004 prediction model with an added factor, A, which accounts for effects of SCC.

$$\varepsilon_{sh} = -k_s k_{hs} \left(\frac{t}{55+t} \right) 0.56 \times 10^{-3} \times A \quad (\mu\varepsilon) \quad (2.44)$$

$$k_{hs} = 2.00 - 0.0143H \quad (2.45)$$

$$k_s = \left[\frac{\frac{t}{26e^{0.0142(V/S)+t}}}{\frac{t}{45+t}} \right] \left[\frac{1064-3.70(V/S)}{923} \right] \quad (2.46)$$

$$A = \begin{array}{ll} 0.918 & \text{for Type I/II cement} \\ 1.065 & \text{for Type III cement} \end{array} \quad (2.47)$$

Where: ε_{sh} is the calculated shrinkage strain at a given age, k_s is the size factor, k_{hs} is the humidity factor, H is relative humidity in percent, t is drying time in days, V/S is the volume to surface area ratio, and A is the cement type correction factor.

2.5.2. Shindler, et. al. The goal of this project was to investigate the shrinkage potential of typical mixes used in precast/prestressed concrete construction. Twenty-one SCC mixes were tested along with two conventional mixes. The specimens tested were 3 in. (76.2 mm) by 3 in. (76.2 mm) by 11.25 in. (285.75 mm) prisms. They were cured in a lime bath for seven days prior to drying. The results suggest very little difference in 28 day shrinkage between the SCC and conventional mixes. At 112 days, the SCC mixes performed better on average than the conventional mixes.

2.5.3. Fernandez-Gomez and Landsberger. Experimental shrinkage results were gathered from 25 published investigations. The database compiled included results from 93 SCC mixes and 30 conventional concrete (CC) mixes. The results were analyzed in order to determine which shrinkage model best fit the data. The models analyzed were CEB-FIP 90, ACI 209, B3, GL 2000, and the Spanish EHE model. The Spanish EHE model is based on the CEB-FIP 90 model, however it doesn't include the factor accounting for cement type. The data was also analyzed to determine which material or mix parameters most influenced shrinkage strain. It was concluded that, based on three statistical models (best-fit line, residual analysis, and coefficient of variation), the B3 and ACI 209 models best predicted shrinkage results for both SCC and CC.

2.5.4. Long, et. al. The goal of this study was to develop equations to predict mechanical properties, workability, and visco-elastic properties of SCC. This was accomplished by evaluating 16 different SCC mixes and determining the key parameters which effect the desired properties. The parameters evaluated were the binder content, binder type, w/c, viscosity modifying admixture (VMA) content, and sand to aggregate

ratio (S/A). Using statistical analysis of the data obtained, the following equations were developed. The variables in the equations are defined according to **Table 2.2**.

Table 2.2 – Coded Values for Eqs. 2.48 – 2.49

Absolute	Coded		
	-1	0	+1
Binder content (BC) (kg/m ³)	440	470	500
Binder type (BT)	Type MS	Type MS + HE	Type HE + 20% FA
w/cm	0.34	0.37	0.40
VMA content (mL/100 kg CM)	0	50	100
Sand-to-aggregate ratio (S/A) By volume	0.46	0.50	0.54

Conversion: 1 kg/m³ = 1.686 lb/yd³
1 mL/100kg = 1.707 fl. oz./100 lb.

56 day autogenous shrinkage:

$$\begin{aligned} \mu\epsilon = & +201 + 67.1 \text{ BT} - 40.6 \text{ w/cm} - 18.8 (\text{BC} \cdot \text{w/cm}) \\ & + 17.8 (\text{BC} \cdot \text{S/A}) \quad (\mu\epsilon) \end{aligned} \quad (2.48)$$

112 day drying shrinkage:

$$\begin{aligned} \mu\epsilon = & +554 - 58.1 \text{ w/cm} + 48.4 \text{ BC} + 46.2 (\text{w/cm} \cdot \text{VMA}) \\ & + 41.9 (\text{w/cm} \cdot \text{BT}) - 40.6 (\text{BC} \cdot \text{VMA}) + 37.4 \text{ S/A} \\ & + 30.8 (\text{VMA} \cdot \text{BT}) \quad (\mu\epsilon) \end{aligned} \quad (2.49)$$

2.6. HVFA SHRINKAGE RESEARCH

Shrinkage of concrete containing fly ash has been researched extensively. The sections below present the data collected and results compiled from research programs into shrinkage of HVFA.

2.6.1. Atis. Six concrete mixes were tested for shrinkage strain at ages up to 6 months. Two mixes were conventional concrete, two had a fly ash replacement of 70% by mass of cement, and the final two mixes had a fly ash replacement of 50% by mass of cement. The mix designs used in this project are shown in **Table 2.3**. Each pair of mixes (OPC, 70%, and 50%) had one mix which was considered roller compacted concrete (RCC) and had a slump of zero. The other mix contained superplasticizer which produced a mix which was practically flowable. At every age of testing and for each type of mix, RCC and flowable, except at 14 days for the flowable mixes, the measured shrinkage strain decreased as the fly ash replacement percentage increased. The results show that concrete made with superplasticizer showed higher shrinkage strains than concrete made without superplasticizer. It was also concluded that, because of HVFA concrete's lower shrinkage strain, the number of joints in concrete pavement construction could be reduced by the use of HVFA concrete. The experimental results are shown in **Table 2.4**.

Table 2.3 - Mix Designs (Atis 2003) (kg per cubic meter)

Mix	M1	M2	M3	M4	M5	M6
Cement (kg)	400	400	120	120	200	200
Fly ash (kg)	---	---	280	280	200	200
Sand (kg)	600	600	600	600	600	600
Gravel (kg)	1200	1200	1200	1200	1200	1200
Water (L)	136	128	112	116	132	120
Optimum W/C ratio	0.32	0.32	0.29	0.29	0.30	0.30
Actual W/C ratio	0.34	0.32	0.28	0.29	0.33	0.30
Superplasticizer	5.6	---	5.6	---	5.6	---
Flow table (mm)	560	0	570	0	600	0

Conversion: $1 \text{ kg/m}^3 = 1.686 \text{ lb/yd}^3$

Table 2.4 - Experimental Shrinkage Results (Atis 2003) (microstrain)

Drying Time	M1	M2	M3	M4	M5	M6
1 day	86	72	56	34	63	38
3 days	134	122	94	69	109	88
7 days	172	148	144	100	153	113
14 days	225	190	164	141	192	125
28 days	347	265	231	163	256	169
56 days	390	296	294	200	319	213
3 months	488	334	350	225	363	256
6 months	554	385	394	263	413	294

2.6.2. Termkhajornkit, et. al. One ordinary Portland cement mix and three different kinds of fly ash mixes were tested to determine autogenous shrinkage of each mix. Fly ash replacement of 25% and 50% were used for two of the mixes, while the third had only a 50% replacement mix. In order to isolate autogenous shrinkage, the specimens were cast in molds and sealed to avoid evaporation. Strain was measured using a strain gauge placed in the center of the mold with concrete cast around it. The samples were kept in a controlled chamber with constant humidity and temperature. For the two mixes where the fly ash replacement was varied, the higher level (50% replacement) mix showed a significant reduction in measured shrinkage strain. Interestingly, all three mixes with 50% replacement outperformed the conventional mixes, while both 25% replacement mixes underperformed the conventional mixes.

2.6.3. Gao, et. al. RCC concrete typical to dam and pavement construction was tested for shrinkage strain. Shrinkage data was recorded for one baseline mix and one equivalent mix with a 50% cement replacement with fly ash. It was concluded that, at 150 days, the shrinkage strains of the 50% replacement mix was approximately 33% less than that of the specimen without fly ash.

2.6.4. Nath and Sarker. Two different concrete series, labeled as series A and B in this study, were tested for drying shrinkage up to 180 days. Both series had one mix with no fly ash replacement, one mix with 30% replacement, and one mix with 40% replacement. Series A was designed in a way that all three mixes attained similar 28 day compressive strengths. Series B was designed so that all three mixes had an identical water to total binder content ratio (w/b) of 0.29. The results of series A show that, with varying w/b and similar strength, fly ash concretes show less shrinkage as the replacement is increased. Series B shows that with an increase in total cementitious material at a constant w/b, the shrinkage strains shown at 180 days of fly ash mixes are very similar to the control mix. Results are shown in **Figures 2.2 – 2.3**.




Figure 2.2 - Series A Shrinkage Results (adapted from Nath and Sarker)




Figure 2.3 - Series B Shrinkage Results (adapted from Nath and Sarker)

2.7. CREEP OF CONCRETE

2.7.1. Definition of Creep. Creep of concrete is defined as “the time-dependent increase in strain under sustained constant load taking place after the initial strain at loading.” (ACI 209.1R-05). Initial strain is the short term strain at the moment of loading. Initial strain is difficult to determine as it is very dependent on the duration and rate of initial load and there is no clear distinction between initial strain and creep strain. Creep strain can be broken up into two parts, basic creep and drying creep. Basic creep is “the increase in strain under sustained constant load of a concrete specimen in which moisture losses or gains are prevented.” Even after 30 years of measurement on sealed concrete specimens, it had yet to be determined if basic creep approaches an ultimate value. Drying creep is the additional creep occurring in a specimen exposed to the environment and allowed to dry. The effects of creep can be expressed in three ways.

The first is similar to that of shrinkage, where creep strain is simply expressed in terms of microstrain (strain $\times 10^{-6}$). The second way is called the creep coefficient. The creep coefficient is the ratio of creep strain to the initial strain at loading. The third is specific creep. Specific creep is the ratio of microstrain to applied load (psi).

2.7.2. Factors Affecting Creep. Like shrinkage, creep is affected by numerous material, mix design, environmental, and construction related factors. Similar to shrinkage, the amount, size, gradation, and properties of the aggregate are very influential on creep of concrete. An increase in aggregate volume will decrease creep. Aggregate gradation is believed to influence creep of concrete because of its relation to changes in overall aggregate volume. The size of aggregate affects bond between paste and aggregate, which controls stress concentration and microcracking. Unlike shrinkage, which is primarily affected by properties of the paste, creep is very dependent on the elastic properties of the aggregate. Concretes with aggregate that have a lower modulus of elasticity generally have higher creep. The primary environmental factor in creep is relative humidity. As relative humidity increases, drying creep significantly decreases. Specimens in environments where drying cannot occur may have only one quarter of the creep of concrete which is allowed to dry. The effects of construction and design on creep are slightly different than shrinkage. One similarity is that increased curing time will decrease creep strain. Unlike shrinkage, basic creep is not affected by the size and shape of the member. The factor that most affects creep is the load applied to the specimen. The magnitude of the load, and the age at which the load is first applied are very important. Loads up to $0.40f_c$ are considered to be linearly related to creep. Finally, concrete loaded at later ages has lower creep.

2.8. CREEP MODELS

As with shrinkage, considerable research has been done and models developed to predict the creep potential of concrete. The following sections will present various models for calculating creep. This includes industry models developed for use with conventional concrete as well as models developed specifically for self-consolidating concrete.

2.8.1. ACI 209R-92. This model is based on the same research as the ACI 209 shrinkage model. The standard conditions as shown in **Table 2.1** apply to creep as well. **Eq. 2.50 – 2.52** represent the general model for concrete meeting the standard conditions. If standard conditions are met, γ_c is taken to be equal to 1. Like the shrinkage model, if any or all of the standard conditions are not met, the model modification factors must be used as shown in **Eq. 2.50 – 2.59**.

$$\Phi(t, t_0) = \frac{(t-t_0)^\psi}{d+(t-t_0)^\psi} \Phi_u \quad (2.50)$$

$$\Phi_u = 2.35\gamma_c \quad (2.51)$$

$$d = 26.0e^{\{0.36(V/S)\}} \quad (2.52)$$

$$\gamma_c = \gamma_{c,to} \gamma_{c,RH} \gamma_{c,vs} \gamma_{c,s} \gamma_{c,\psi} \gamma_{c,\alpha} \quad (2.53)$$

$$\gamma_{c,to} = \begin{cases} 1.25t_0^{-0.118} & \text{for moist curing} \\ 1.13t_0^{-0.094} & \text{for steam curing} \end{cases} \quad (2.54)$$

$$\gamma_{c,RH} = 1.27 - 0.67h \quad (2.55)$$

$$\gamma_{c,vs} = \frac{2}{3}(1 + 1.13e^{\{-0.54(V/S)\}}) \quad (2.56)$$

$$\gamma_{c,s} = 0.82 + 0.067s \quad (2.57)$$

$$\gamma_{c,\psi} = 0.88 + 0.0024\psi \quad (2.58)$$

$$\gamma_{c,\alpha} = 0.46 + 0.09\alpha \geq 1 \quad (2.59)$$

Where: $\Phi(t,t_0)$ is the calculated creep coefficient at a given age, Φ_u is the calculated ultimate creep coefficient, t is the age of the specimen in days, γ_{c,t_0} is the curing condition correction factor, t_0 is the age at which the specimen is loaded in days, $\gamma_{c,RH}$ is the humidity correction factor, h is relative humidity in decimals, $\gamma_{c,vs}$ is the size correction factor, V/S is the volume to surface area ratio, $\gamma_{c,s}$ is the slump correction factor, s is slump in inches, $\gamma_{c,\psi}$ is the fine aggregate correction factor, ψ is the ratio of fine aggregate to total aggregate by weight expressed as percentage, $\gamma_{c,\alpha}$ is the air content correction factor, and α is the air content in percent. For shape and size effects to be totally considered, d is to be determined using **Eq. 2.52** and ψ assumed to be equal to 1.0. Otherwise, average values of $d=10$ and $\psi=0.6$ are to be assumed.

2.8.2. NCHRP Report 496. This proposed creep model was developed in a similar manner to that of the NCHRP Report 496 shrinkage model. The correction factors that are identical to those used in the corresponding shrinkage model have already been defined in Section 2.4.2. The model is shown in **Eq. 2.60 – 2.66**.

$$\psi(t, t_i) = 1.90\gamma_{cr} \quad (2.60)$$

$$\gamma_{cr} = k_{td}k_{la}k_s k_{hc}k_f \quad (2.61)$$

$$k_{td} = \frac{t}{61-4f'_{ci}+t} \quad (2.62)$$

$$k_{la} = t_i^{-0.118} \quad (2.63)$$

$$k_s = \frac{1064-94V/S}{735} \quad (2.64)$$

$$k_{hc} = 1.56 - 0.008H \quad (2.65)$$

$$k_f = \frac{5}{1+f'_{ci}} \quad (2.66)$$

Where: $\psi(t, t_i)$ is the calculated creep coefficient at a given age, k_{td} is the time development factor, t is the age of the concrete in days, k_{la} is the loading factor, t_i is the age at which creep specimen is loaded in days, k_s is the size factor, V/S is the volume to

surface area ratio, k_{hc} is the humidity factor, H is the average ambient relative humidity in percent, k_f is the concrete strength factor, and f'_{ci} is the specified compressive strength of concrete in ksi.

2.8.3. CEB-FIP 90. The following equations apply to the creep model as developed jointly by CEB and FIP as presented in the CEB-FIP Model Code 1990.

$$\Phi(t, t_0) = \Phi_0 \beta_c(t - t_0) \quad (2.67)$$

$$\Phi_0 = \Phi_{RH} \beta(f_{cm}) \beta(t_0) \quad (2.68)$$

$$\Phi_{RH} = 1 + \frac{1 - RH}{0.46 \left(\frac{2A_c}{100u} \right)^{1/3}} \quad (2.69)$$

$$\beta(f_{cm}) = \frac{5.3}{(f_{cm}/10)^{0.5}} \quad (2.70)$$

$$\beta(t_0) = \frac{1}{0.1 + t_0^{0.2}} \quad (2.71)$$

$$\beta_c(t - t_0) = \left[\frac{(t - t_0)}{\beta_H + (t - t_0)} \right]^{0.3} \quad (2.72)$$

$$\beta_H = 150 \{ 1 + (1.2RH)^{18} \} \left(\frac{2A_c}{100u} \right) + 250 \leq 1500 \quad (2.73)$$

Where: $\Phi(t, t_0)$ is the calculated creep coefficient at a given age, Φ_0 is the notional creep coefficient, β_c is the coefficient to describe the development of creep with time after

loading, t is the age of concrete in days, t_0 is the age of concrete at loading in days, RH is the relative humidity in decimals, A_c is the cross section area in mm^2 , u is the perimeter in contact with the atmosphere in mm, and f_{cm} is the mean compressive strength of concrete at the age of 28 days in MPa.

2.8.4. GL 2000. As with the GL 2000 shrinkage model, the following creep model was published in the ACI materials journal under the title “Design Provisions for Drying Shrinkage and Creep of Normal-Strength Concrete”.

$$\Phi_{28} = \Phi(t_c) \left[2 \left(\frac{(t-t_c)^{0.3}}{(t-t_c)^{0.3}+14} \right) + \left(\frac{7}{t_0} \right)^{0.5} \left(\frac{t-t_c}{t-t_c+7} \right)^{0.5} + 2.5(1 - 1.086h^2) \left(\frac{t-t_0}{t-t_0+97(V/S)^2} \right)^{0.5} \right] \quad (2.74)$$

$$\Phi(t_c) = \left[1 - \left(\frac{t-t_c}{t-t_c+97(V/S)^2} \right)^{0.5} \right]^{0.5} \quad (2.75)$$

Where: Φ_{28} is the calculated creep coefficient at a given age, $\Phi(t_c)$ is a factor that takes into account drying before loading, t is age of concrete in days, t_c is the age of concrete when drying begins, t_0 is the age the concrete was loaded, h is humidity in decimals, and V/S is the volume to surface area ratio in mm.

2.9. SCC CREEP RESEARCH

2.9.1. NCHRP Report 628. As with shrinkage, NCHRP 628 presents an SCC specific creep prediction model which is a modified version of the AASHTO 2004 model. **Eq. 2.76 – 2.81** are used to calculate creep of SCC using the proposed modification factor.

$$\psi(t, t_i) = 1.9k_{vs}k_{hc}k_fk_{td}k_i^{-0.118} \times A \quad (2.76)$$

$$k_{vs} = 1.45 - 0.0051(V/S) \geq 0 \quad (2.77)$$

$$k_{hc} = 1.56 - 0.08H \quad (2.78)$$

$$k_f = \frac{35}{7+f'_{ci}} \quad (2.79)$$

$$k_{td} = \left(\frac{t}{61 - 0.58f'_{ci} + t} \right) \quad (2.80)$$

$$A = \begin{cases} 1.19 & \text{for Type I/II cement} \\ 1.35 & \text{for Type III cement} \end{cases} \quad (2.81)$$

Where: $\psi(t, t_i)$ is the calculated creep coefficient, k_{vs} is the volume to surface area factor, V/S is the volume to surface area ratio, k_{hc} is the humidity correction factor, H is relative humidity in percent, k_f is the concrete strength factor, f'_{ci} is the concrete compressive strength at time of loading in MPa, k_{td} is the time development factor, t is age of concrete since loading in days, and A is the cement type correction factor.

2.9.2. Long and Khayat. A total of 16 SCC mixes were tested for creep. The purpose of this experimental program was to determine the key mixture design and material selection parameters that most affect creep of SCC. Additionally, conclusions were made on which current creep prediction model best estimates creep of SCC. It was found that the binder type was most influential on creep of SCC, followed by binder content. The model that best predicts creep of SCC was found to be CEB-FIP 90. The

modified AASHTO model described in 2.9.1. was also determined to successfully predict creep of SCC.

2.9.3. Long, et. al. The same study as described in Section 2.5.4 was also done to develop a prediction equation for creep strain of SCC. The following equation was developed to predict creep of SCC, with the same variable definitions as shown in **Table 2.2.**

112 day creep strain ($\mu\epsilon$):

$$\begin{aligned} &+1036 + 73.6 BT + 40.7 (VMA \cdot BT) + 38.8 BC \\ &+34.9 (w/cm \cdot BT) - 32.9 (BC \cdot S/A) \end{aligned} \quad (2.82)$$

2.10. HVFA CREEP RESEARCH

Research has shown that the replacement of Portland cement with fly ash produces concrete which exhibits lower long term creep. Suggested reasons why this is true are discussed in the following sections.

2.10.1. ACI 232.2R-03. The ACI 232.2R committee report cites several sources that have researched creep of fly ash concrete. Lane and Best showed that, when formulated to have the same compressive strength at the age of testing, fly ash concretes display lower shrinkage. It is suggested that this is due to the higher late age strength of fly ash concrete.

2.10.2. Alexander, et. al. Concrete with 25% fly ash replacement was tested for creep up to the age of 6 years. The specimens were tested at loads of 25% and 40% of 28 day compressive strength. A control conventional concrete mix was also tested

simultaneously. All specimens tested had a strength of 4000 psi (27.58 MPa) at 28 days. The results show that concrete without fly ash showed 50% higher creep than concrete which had 25% fly ash replacement. These results were recorded at two years of age, and remained unchanged up to six years.

2.11. Application of Shrinkage and Creep

2.11.1. Prestress Loss. Prestress loss is “the loss of compressive force acting on the concrete component of a prestressed concrete section.” (NCHRP 426) The ability to accurately predict the prestress loss in beams is very dependent on the ability to predict the beam’s shortening due to shrinkage and creep. Shortening of the beam reduces the tensile force in the prestressed reinforcement and must be accounted for in design. NCHRP 426 names three components which significantly affect the prestress loss in pretensioned concrete members which directly relate to shrinkage and creep. These components are:

1. Instantaneous prestress loss due to elastic shortening at transfer of force from prestressed reinforcement to concrete.
2. Long-term prestress loss due to shrinkage and creep of concrete and relaxation of prestressing strands between the time of transfer and deck placement.
3. Long-term prestress loss between the time of deck placement to the final service life of the structure due to shrinkage and creep of the girder.

Figure 2.4 shows the prestress loss over the life cycle of a pretensioned concrete girder. The loss between points D and E represent the loss due to creep, shrinkage, and relaxation of prestressing strands.




Figure 2.4 - Stress vs. Time for Prestressed Bridge Girder (Tadros et. al. 2003)

2.11.2. Load Effects. The procedures in “Design of Continuous Highway Bridges with Precast, Prestressed Concrete Girders” published by the Portland Cement Association (PCA) take into account additional moments due to shrinkage and creep when determining loads for design. In this method, fixed end moments due to creep and end driving moments due to shrinkage are calculated. These applied moments result from a continuity connection being made at supports by the placement of the bridge deck. The placement restricts free rotation of the beams and therefore produces moment in the connection. The moments calculated by this method are then added to all other load effects at all sections for determination of the ultimate design load. The shrinkage driving moment calculation is done by first calculating theoretical ultimate shrinkage values for the beam and the slab. The differential shrinkage between the beam and slab are then used to determine an applied moment due to shrinkage. The applied moment due to creep results from prestressed creep and dead load creep. Theoretical creep

coefficients are calculated for the time before and after deck placement. The creep that occurs after deck placement is what contributes to the applied moment.

2.11.3. Beam Deflection. Shrinkage and creep must also be accounted for when calculating long term deflection of flexural members. Eq. 9-11 of ACI 318-08, shown here as **Eq. 2.83**, accounts for long term sustained loads. This factor is multiplied by the immediate deflection caused by the load considered.

$$\lambda_{\Delta} = \frac{\xi}{1+50\rho'} \quad (2.83)$$

Where: λ_{Δ} is the multiplier for additional deflection due to long-term effects, ξ is the time dependent factor for sustained load, and ρ' is compression reinforcement ratio.

2.12. CONCRETE ABRASION

2.12.1. Definition of Concrete Abrasion. Abrasion is the physical wearing down of a material. The most common sources of abrasion of concrete structures are by the friction between vehicle tires and concrete pavement road surfaces, and by water flows over exposed dam or bridge footings. Concrete abrasion leads to a decrease in member thickness which can lead to cracking or failure of the structure (Atis).

2.12.2. Factors Affecting Concrete Abrasion. Several material properties and construction factors can affect the abrasion resistance of concrete. The concrete strength is the most influential property in regards to abrasion resistance. The properties of the aggregate are also very important in a concrete's resistance to abrasion. The

surface finish and whether or not a hardener or topping is used effects abrasion resistance as well (Naik et. al.).

2.13. SCC ABRASION RESEARCH

Little research has been done on self-consolidating concrete's abrasion resistance relative to conventional concrete. This is most likely due to the fact that the use of SCC is not motivated primarily by its hardened properties but by its fresh concrete properties. Also SCC members are less likely to be exposed to abrasive action as SCC is normally reserved for use in pre-stressed members such as girders which are typically not exposed to vehicles or water.

2.14. HVFA ABRASION RESEARCH

There is considerable data available on the abrasion resistance of HVFA. The motivation for research of HVFA abrasion resistance is that HVFA has been proposed as a possible material for paving.

2.14.1. Naik, et. al. The objective of this testing program was to determine the abrasion resistance of HVFA mixes. Three sources of fly ash were used. Mixes containing 40%, 50%, and 60% fly ash were tested according to a modified version of ASTM C944 for each source along with one convention concrete mix. In this study, depth of wear was used as the measure of value. Results show that above 50%, abrasion resistance of fly ash mixes is slightly lower than that of the reference mix. Results also show that, above all, the concrete's strength was the most influential factor in abrasion resistance.

2.14.2. Atis. The objective of this program was to determine the abrasion resistance of HVFA for use as a pavement material. Five different mixes were tested. One baseline mix, two 50% HVFA mixes, and two 70% HVFA mixes were tested in accordance to BSI 1993 – British Standards Institute “Method for determination of aggregate abrasion value (AAV).” This test method is similar to ASTM C944, which was followed during testing of specimens in this report. Mass loss was the measure of value in this test. Again, results show that abrasion resistance is primarily dependent on the concrete’s strength rather than fly ash content. However results also suggest that at higher strengths, the 70% fly ash mix showed higher resistance than the 50% mix and conventional mix, but at lower strengths the opposite is true.

3. RESEARCH PROGRAM

3.1. MIX DESIGNS

3.1.1. SCC. The SCC testing program consisted of four mixes, two being SCC with two as conventional concrete equivalents to the SCC mixes. The naming convention used in the SCC testing program begins with either C (conventional concrete) or S (SCC). The next number indicates the target 28 day compressive strength, in ksi. Following the dash is a number indicating the ratio of fine aggregate to total aggregate by weight. It finishes with L, indicating the type of coarse aggregate used, dolomitic limestone. The baseline normal strength concrete tested was MoDOT A-1 (C6-58L). The A-1 mix was used as the comparative mix to the normal strength SCC mix (S6-48L). Both mixes had identical w/c and air content, with the aggregate ratio and HRWR dosage adjusted. The S6-28L mix design was based on the average of survey responses from regional precast plants. The baseline high strength concrete (C10-58L) mix design was based on research done by Myers and Carrasquillo (2000) at the University of Texas at Austin. The high strength SCC mix (S10-48L) was designed based on the C10-58L mix design and finalized after trial batches were made and adjusted. The designs of the mixes tested can be found in **Table 3.1** along with measured 28 day compressive strength (f'_c) and modulus of elasticity (MOE). All mixes and specimens were batched and cast in the Missouri University of Science and Technology (Missouri S&T) concrete lab located in Butler-Carlton Hall. All testing was done in the High Bay structures lab also located in Butler-Carlton Hall on the campus of Missouri S&T.

Table 3.1 - SCC Test Program Mix Designs and Mechanical Properties

Material	Amount (per cubic yard)			
	C6-58L	S6-48L	C10-58L	S10-48L
Water	277.5 lb.	277.5 lb.	315 lb.	315 lb.
Cement	750 lb. (Type I)	750 lb. (Type I)	840 lb. (Type III)	840 lb. (Type III)
Course Aggregate	1610 lb.	1333 lb.	1440 lb.	1192 lb.
Fine Aggregate	1444 lb.	1444 lb.	1043 lb.	1291 lb.
Fly Ash	N/A	N/A	210 lb.	210 lb.
BASF MB-AE-90 (air entrainment)	2.3 fl oz/cwt	1.2 fl oz/cwt	1.25 fl oz/cwt	1.0 fl oz/cwt
BASF Glenium (HRWR)	4.7 fl oz/cwt	6.2 fl oz/cwt	4.9 fl oz/cwt	6.0 fl oz/cwt
f'c (psi)	7,000	5,500	11,000	13,500
MOE (psi)	3,450,000	3,130,000	3,900,000	4,200,000

Conversion: $1 \text{ kg/m}^3 = 1.686 \text{ lb/yd}^3$

1 fl oz = 26.57 mL

1 psi = 6.89 kPa

3.1.2. HVFA. The HVFA testing program consisted of three mixes. The first mix tested was a conventional concrete baseline mix (HVFA-C). The other two were HVFA mixes. Both HVFA mixes had 70% Class C fly ash replacement, one with a relatively high amount of cementitious material (HVFA-H) and the other a relatively low amount of cementitious material (HVFA-L). The HVFA-L mix design was based on research done by Ortega (2010) at Missouri S&T. The HVFA-H mix design was a modification of HVFA-L to include an increased amount of total cementitious material. Both HVFA mixes were batched with the help of Rolla Ready Mix. A partial mix was delivered, with the fly ash, gypsum, calcium hydroxide, and HRWR added upon arrival. The mix designs tested can be found in **Table 3.2** along with the measured 28 day compressive strength (f'c) and modulus of elasticity (MOE). All aggregate weights found in **Table 3.2** are based on SSD conditions.

Table 3.2 - HVFA Test Program Mix Designs and Mechanical Properties

Material	Amount (per cubic yard)		
	HVFA-C	HVFA-H	HVFA-L
Water	226 lb.	321 lb.	226 lb.
Cement (Type I)	564 lb.	219 lb.	155 lb.
Coarse Aggregate (3/4" JC Dolomite)	1860 lb.	1754 lb.	1754 lb.
Fine Aggregate (Missouri River Sand)	1240 lb.	1080 lb.	1080 lb.
Fly Ash	N/A	511 lb.	360 lb.
Gypsum	N/A	20.4 lb	14.4 lb.
Calcium Hydroxide	N/A	51.1 lb.	36 lb.
BASF MB-AE-90 (air entrainment)	0.625 fl oz/cwt	0.625 fl oz/cwt	0.625 fl oz/cwt
BASF Glenium 7500 (HRWR)	3.0 fl oz/cwt	N/A	3.0 fl oz/cwt
f'_c (psi)	5,400	3,100	3,500
MOE (psi)	3,386,000	3,475,000	3,163,000

Conversion: $1 \text{ kg/m}^3 = 1.686 \text{ lb/yd}^3$

1 fl oz = 26.57 mL

1 psi = 6.89 kPa

3.2. SHRINKAGE AND CREEP SPECIMEN CONSTRUCTION

3.2.1. Shrinkage and Creep Specimens. Both shrinkage and creep testing were done using identical specimens. Although only four specimens per mix were necessary for testing (two each for shrinkage and creep), six specimens per mix were cast in case any specimens were damaged during de-molding. These specimens were fabricated and prepared as described below.

3.2.2. Shrinkage and Creep Molds. The molds for the shrinkage and creep specimens were 4 in. diameter PVC pipe adhered to a plywood base. The PVC was cut into 24 in. sections with care being taken to ensure all cuts were made so that the mold would sit flush and orthogonal to the base. The PVC was also notched on opposite sides. The notches made de-molding much easier and significantly reduced the possibility of

damaging the specimens during de-molding. Once prepared the PVC was adhered to a 1 ft. (304.8 mm) by 1 ft. (304.8 mm) plywood base using a waterproof silicon sealant. The completed molds were allowed to sit for at least 24 hours before use to allow for the sealant to fully set up. **Figure 3.1** shows a completed shrinkage and creep mold.



Figure 3.1 - Shrinkage and Creep Form

3.2.3. Shrinkage and Creep Specimen Casting. Specimens were consolidated in a manner similar to that prescribed in ASTM C31 “Standard Practice for Making and Curing Concrete Test Specimens in the Field” for a 6 in. diameter cylinder. Consolidation and vibration were performed when necessary. The specimens were cast

in three layers of approximately equal depth and were rodded 25 times per layer. External vibration was also performed after each layer was rodded using an electric handheld concrete vibrator as needed. Specimens were moist cured until de-molded and prepared.

3.2.4. Shrinkage and Creep De-Molding and Preparation. All specimens were de-molded within 24 hours of their initial set time. De-molding was done by first cutting through the notched section with a utility knife. A hammer and chisel were then used to split the mold and remove it from the concrete. Creep specimens were sulfur capped on both ends in preparation for loading at 28 days. Shrinkage specimens were sulfur capped on only the bottom end, allowing for stability and more accurate readings.

3.2.5. Shrinkage and Creep Data Acquisition. A demountable mechanical strain gauge (DEMEC) was used to measure strain in the concrete. DEMEC points, small pre-drilled stainless steel discs, were adhered to the surface of the specimen. They were arranged in three vertical lines of five points, 120° apart, as shown in **Figure. 3.2**. This arrangement allowed for 9 readings to be taken per specimen. The average of all readings taken per specimen was taken as the value to be used for strain calculation. The points in one line per specimen were adhered using gel control super glue. The instant hardening allowed for initial readings to be made on each specimen as soon as possible. The remaining points were adhered using concrete/metal epoxy, which took up to 24 hours to fully harden for accurate reading to be taken. The points adhered with super glue were later protected using the epoxy.




Figure 3.2 – Shrinkage and Creep Specimens and DEMEC Point Arrangement (Myers and Yang, 2005)

3.3. ABRASION SPECIMEN CONSTRUCTION

One specimen per mix was cast for abrasion test. Each specimen was large enough so that three replicate abrasion tests could be done for each mix. Abrasion specimens measured 6 in. (152.4 mm) by 16 in. (406.4 mm) by 3.5 in. (88.9 mm) and were cast in a mold made from wooden 2x4 sections and attached to a plywood base. The baseline and HVFA mixes were consolidated similar to that prescribed in ASTM C31 “Standard Practice for Making and Curing Concrete Test Specimens in the Field” for a 6 in. (152.4 mm) wide beam. External vibration was used as necessary. To ensure that abrasion tests on all specimens were consistent, every specimen tested was finished by the same individual using a hand trowel. Specimens were moist cured until tested. All testing was performed on the top finished surface of the specimen.

3.4. TESTING PROCEDURES

3.4.1. Shrinkage Testing Procedures. A modified version of ASTM C157 “Standard Test Method for Length Change of Hardened Hydraulic-Cement Mortar and Concrete” was used to determine the shrinkage of the concrete specimens. Until the age of loading for creep, four specimens were used for shrinkage determination. At 28 days, two of these specimens were transferred to creep frames, leaving two remaining specimens to be tested for long term shrinkage. Nine strain readings could be taken per specimen, with the average of all readings taken as the value to be used for shrinkage calculation. Strain was determined using the DEMEC readings and calculated by **Eq. 3.1** as found in “Simplified Instructions for Using a Digital DEMEC Gauge”. An example of a DEMEC reading being taken on a specimen is in **Figure 3.3** Readings were normalized by taking a reading on the reference bar, shown in **Figure 3.4** with a reading taken on the reference bar shown in **Figure 3.5**. Shrinkage strain experienced during the first day after demolding was estimated based on linear interpolation of subsequent strain values, as calculated by **Eq. 3.1**

$$\Delta\varepsilon_s = G((R_i - R_0) - (D_i - D_0)) \quad (\mu\varepsilon) \quad (3.1)$$

Where: $\Delta\varepsilon_s$ is the change in strain from one reading to the next, G is the gauge factor shown in **Figure 3.6**, 0.400×10^{-5} strain per division (4 microstrain), D_0 is the datum reading on the reference bar, D_i is the subsequent reading on the reference bar, R_0 is the datum reading on the tested material, and R_i is the subsequent reading on the tested

material. Gauge units are the digital gauge reading without the decimal point. For example, **Figure 3.7** shows a reading of 2.523 which equates to 2523 gauge units.



Figure 3.3 – DEMEC Reading Taken on Specimen



Figure 3.4 - Reference Bar



Figure 3.5 - Reading Taken on Reference Bar



Figure 3.6 - Gauge Factor Used for Shrinkage and Creep Calculations



Figure 3.7 - Example DEMEC Gauge Reading

3.4.2. Creep Testing Procedures. A modified version of ASTM C512 “Standard Test Method for Creep of Concrete in Compression” was used to determine the creep of the concrete specimens tested. Until the age of loading, creep specimens acted as shrinkage specimens. This is a modification of ASTM C512, as the specimens were not moist cured beyond the time of de-molding. Additionally, humidity was not controlled however it was recorded.

At 28 days, representative specimens were tested according to ASTM C39 “Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens” and ASTM C469 “Standard Test Method for Static Modulus of Elasticity and Poisson’s Ratio of Concrete in Compression.” Creep specimens were then loaded to 40% of their measured 28 day compressive strength in the creep frames shown in **Figures 3.8 – 3.9**. The design of the creep frames was based on research done by Myers and Yang (2005).




Figure 3.8 - Schematic of Creep Loading Frame (Myers and Yang, 2005)
(1 in = 25.4 mm)



Figure 3.9 - Creep Loading Frame with Specimen

Measurements taken on creep specimens were done in the exact way as with the shrinkage specimens. **Eq. 3.2** was used to determine the change in strain between one creep reading to the next. Using the calculated creep strain, the coefficient of creep could be determined by **Eq. 3.3**. Creep and shrinkage readings for like specimens were taken at the same interval. Readings were also taken immediately before and after loading to determine initial elastic strain due to loading. **Figure 3.10** shows a reading being taken on a creep specimen.

$$\Delta\varepsilon_c = G((R_i - R_0) - (D_i - D_0)) - \Delta\varepsilon_s \text{ (}\mu\varepsilon\text{)} \quad (3.2)$$

Where: $\Delta\varepsilon_c$ is the change in creep strain between readings.

$$\Phi(t, t_0) = \varepsilon_t / \varepsilon_i \quad (3.3)$$

Where: $\Phi(t, t_0)$ is the measured creep coefficient at a given age, ε_i is the measured strain due to initial loading of the specimen, ε_t is the measured creep strain at a given age.



Figure 3.10 - Reading Taken on Creep Specimen

3.4.3. Abrasion Resistance Testing Procedures. ASTM C944 “Standard Test Method for Abrasion Resistance of Concrete or Mortar Surfaces by the Rotating-Cutter Method” was used to determine abrasion resistance. A schematic of the rotating cutter used is shown in **Figure 3.11**, which is taken from ASTM C944. The actual rotating cutter is shown in **Figure 3.12**. Abrasion specimens were moist cured until testing at 28 days age. The two HVFA mixes were additionally tested after an additional 10 weeks of moist cure to further investigate how the late age strength gain of HVFA affected abrasion resistance. One specimen per mix was constructed, which allowed for three abrasion tests. One abrasion test consisted of three abrasion cycles. Each cycle lasted two minutes. A load of 44lb, defined as a double load in ASTM C944, was applied at a rate of 300 rpm using a drill press as shown in **Figure 3.13**. After each cycle, mass loss (mg) was recorded by subtracting the final weight from the initial weight. Each cycle per test was done on the same spot. After completion of each abrasion test, the average depth of wear (mm) was measured using digital calipers. The average depth of wear was calculated from a total of eight depth measurements relative to the adjacent untested surface, four taken on the outer perimeter of the tested surface and four taken around the inner perimeter, at the points indicated in **Figure 3.14**. The measurements were made using a digital caliper. On the day of testing, the specimen was removed from moist cure and surface dried by blotting with paper towels. This was done to avoid any mass loss due to moisture loss. A completed specimen after all three abrasion tests is shown in **Figure 3.15**.




Figure 3.11 - Schematic of Abrasion Rotating Cutter (ASTM C944)
(1 in = 25.4 mm)



Figure 3.12 - Rotating Cutter



Figure 3.13 - Abrasion Resistance Test In Progress



Figure 3.14 - Depth of Wear Measurement Points




Figure 3.15 - Abrasion Resistance Specimen After Testing

4. SCC RESULTS AND DISCUSSION

4.1. SHRINKAGE

4.1.1. Results. Figures 4.1 – 4.4 show the experimental data obtained from shrinkage tests of SCC plotted with the various prediction models discussed in Section 2. Figure 4.5 shows the experimental results of all four mixes plotted with one another. In figures where different data sources are together, the source of the data can be found in parentheses after the data label in the legend of its respective figure. All data obtained in this study was gathered at Missouri S&T.

4.1.2. Discussion and Conclusions. For the lower strength variations, C6-58L and S6-48L, the relative shrinkage strains are not consistent with the SCC prediction model found in NCHRP Report 628. This model was a modification of the AASHTO prediction model, with an added factor to account for the effects of SCC. In the NCHRP Report 628 model, SCC made using Type I/II cement should show a reduction in shrinkage strain. The reduction factor in NCHRP Report 628 for SCC with Type I/II cement is 0.918, therefore it is expected that S6-48L would have a reduction in shrinkage strain. The reason for this inconsistency with previous data could be the difference in mix designs used in this project compared to others. Since shrinkage of concrete is most related to shrinkage of paste, it would be expected that mixes with higher paste volumes would experience more shrinkage. Relative to all mixes tested by Schindler, et. al., S6-48L had a greater cement content, fine aggregate content, and FA/CA ratio. In a similar study done by Long, Khayat and Xing, it was concluded that shrinkage is highly affected by binder content. The relatively high binder content and low coarse aggregate content of S6-48L could be the reason for the large shrinkage strains.

For high strength variations, C10-58L and S10-48L, the experimental results are very consistent with previous findings. Schindler, et. al. reported that high strength SCC mixes show a reduction in shrinkage relative to high strength conventional concrete. Therefore it can be expected that, in terms of shrinkage, high strength SCC is an adequate alternative to conventional high strength concrete.

Besides the mix designs, the environment the specimens were exposed to seemed to have a significant effect on shrinkage. As seen in Appendix A, there is a correlation between shrinkage and relative humidity. The unexpected decreases in shrinkage that were measured tend to correspond to days with unusually high relative humidity. This confirms the relationship given by **Eq. 2.1** from ACI 209.1R-05 which states that shrinkage is inversely related to relative humidity.

Comparing the results to previous studies, both SCC mixes perform adequately. **Table 4.1** and **Figure 4.6** show the shrinkage data of S6-48L and S10-48L relative to the database compiled in Fernandez-Gomez and Landsberger, Shindler et. al., and Holsheimer and the equations developed by Long, et.al. The 112 day shrinkage strains calculated from Long et. al. are the 56 day autogenous shrinkage (**Eq. 2.48**) added to the 112 day drying shrinkage (**Eq. 2.49**). This is acceptable as it has been shown that autogenous shrinkage reaches stable values after 56 days (Long, Khayat, and Xing). Results from this study are consistent with the database compiled by Fernandez-Gomez and Landsberger, which includes 93 SCC mixes. At all ages that were tested in this study the results for both S6-48L and S10-48L fall within the limits of the database. When comparing to the shrinkage prediction equations developed by Long et. al., however, S6-48L doesn't seem to perform quite as well. Again, when comparing S10-48L to this

previous SCC shrinkage study, it performs very well. Below is a summary figure showing the SCC mixes tested in this program shown with the databases compiled by Fernandez-Gomez and Landsberger, Shindler et. al., and Holschemacher. The shrinkage from Schindler et. al. is likely lower due to the specimens being submerged in a lime bath for the first 7 days.

Finally, results for the normal strength variations are consistent with the observation made by Holschemacher (2004) that “In the majority of the evaluated data the shrinkage of SCC is 10 to 50% higher than the one of conventional concrete.” At 150 days, S6-48L had experienced 24% greater shrinkage than C10-58L. This trend, however, does not hold true for the high strength variations.




Figure 4.1 - C6-58L Shrinkage Results and Prediction Models




Figure 4.2 - S6-48L Shrinkage Results and Prediction Models




Figure 4.3 - C10-58L Shrinkage Results and Prediction Models




Figure 4.4 - S10-58L Shrinkage Results and Prediction Models




Figure 4.5 - SCC Shrinkage Results (Best fit Logarithmic)




Figure 4.6 – SCC Results with Shrinkage Databases (Fernandez-Gomez, Shindler et. al., and Holschemacher)

Table 4.1 – SCC Results Compared to Eqs. 2.48 – 2.49 by Long et. al.

Specimen	112 Day Measured Shrinkage Strain (microstrain)	112 Day Theoretical Shrinkage Strain (microstrain)
S6-48L	-761	-659
S10-48L	-628	-1029

4.2. CREEP

4.2.1. Results. Creep Results are shown in **Table 4.2** and **Figure 4.7**. In figures where different data sources are together, the source of the data can be found in parentheses after the data label in the legend of its respective figure. For all specimens tested for this study, the notation (S&T) will be used.

Table 4.2 - Summary of SCC Creep Results

Creep Strain (microstrain)				
Specimen	Days After Loading			
	7	14	56	126
C6-58L	282	329	608	862
S6-48L	196	272	592	928
C10-58L	371	452	949	1326
S10-48L	441	557	874	1005
Percentage of 126 Day Creep				
C6-58L	33	38	71	100
S6-48L	21	29	64	100
C10-58L	28	34	72	100
S10-48L	44	55	87	100
Measured Creep Coefficient				
C6-58L	0.387	0.451	0.834	1.18
S6-48L	0.477	0.660	1.44	2.25
C10-58L	0.423	0.516	1.08	1.51
S10-48L	0.388	0.489	0.768	0.883
Specific Creep ($\mu\epsilon/\text{psi}$)				
C6-58L	0.101	0.118	0.217	0.308
S6-48L	0.089	0.124	0.269	0.422
C10-58L	0.085	0.103	0.216	0.302
S10-48L	0.082	0.104	0.163	0.188

Conversion: 1 MPa = 145.04 psi

4.2.2. Discussion and Conclusions. Like the shrinkage results, for normal strength specimens, the conventional concrete variation outperformed SCC. Also like the shrinkage results, for the high strength specimens, SCC outperformed conventional concrete.

For normal strength concrete, these results are supported by every prediction model that was analyzed. Every model predicts that C6-58L would have a lower creep coefficient than S6-48L after 126 days being loaded. The models were not as consistent when predicting the creep behavior of high strength concrete. The model identified by Long and Khayat (2011) as best predicting SCC creep behavior, CEB-FIP 90, does predict the behavior of specimens in this study. CEB-FIP 90 predicts that, like the results, S10-48L would have a lower creep coefficient than C10-58L after 126 days being loaded. Additionally, NCHRP Report 628 (2009), the model which is specifically for SCC, also predicts the same relationship.

In terms of comparing the results to previous research, both specimens performed very well. Long and Khayat (2011) investigated the creep strain on 16 SCC mixes. Eight of these mixes Nos. 1-8, were all very similar to S6-48L in terms of compressive strength, with Nos. 1-4 having a w/c of .34 and Nos. 5-8 with a w/c of .40. As seen on the next page, when plotted against these mixes, as shown in **Figure 4.8**, S6-48L performs very well. The same relationship exists between S10-48L and Nos. 9-12 from Long and Khayat (2011). These mixes have similar amount of cement, however did not achieve the compressive strength of S10-48L. Creep results from S10-48L are shown with mix Nos. 9-12 in **Figure 4.9**. All specimens tested in Long and Khayat (2011) were loaded to 40% of their measured compressive strength, but at 18 hours age. The lower

creep strain experienced by the specimens in this study relative to Long and Khayat are possibly due to the concrete in the study being loaded at a later age when the strength and stiffness has increased relative to that of 18 hour old concrete.




Figure 4.7 – SCC Coefficient of Creep Results




Figure 4.8 – S6-48L Plotted Against Results from Long and Khayat (2011)




Figure 4.9 – S10-48L Plotted Against Results from Long and Khayat (2011)

4.3. ABRASION RESISTANCE

4.3.1. Results. Figures 4.10 – 4.13 show the mass losses recorded after each two minute abrasion cycle for each mix tested. Figure 4.14 shows the cumulative mass loss comparison between the four mixes. Figure 4.15 shows the depth of wear results from abrasion testing. Table 4.3 shows a summary of all results along with measured 28 day compressive strength. One test consisted of three cycles.




Figure 4.10 - C6-58L Mass Loss Results




Figure 4.11 - S6-48L Mass Loss Results




Figure 4.12 - C10-58L Mass Loss Results




Figure 4.13 - S10-48L Mass Loss Results




Figure 4.14 - SCC Mass Loss Results




Figure 4.15 - SCC Depth of Wear Results

Table 4.3 - Summary of Results Shown with 28 Day Measured Compressive Strength

	C6-58L	S6-48L	C10-58L	S10-48L
28 Day Compressive Strength (psi)	7,000	5,500	11,000	13,500
Avg. Mass loss (g)	2.53	5.76	1.99	2.06
Avg. Depth of Wear (mm)	0.59	1.07	0.54	0.47

Conversion: 1 MPa = 145.04 psi

1 lb. = 453.59 g

1 in. = 25.4 mm

4.3.2. Discussion and Conclusions. The results obtained are very consistent with trends found in previous studies. As was concluded in both Atis and Naik, the abrasion resistance of concrete is primarily dependant on compressive strength. For both criteria (mass loss and depth of abrasion), the abrasion resistance of concrete increased as

the compressive strength of the specimens increased, except for the mass loss of S10-48L relative to C10-58L. Additionally, when comparing concrete mixes with the same design strength, the SCC mix generally showed a lower resistance to wear. This is most likely due to the decreased amount of coarse aggregate in the SCC mixes. Based on observations during and after testing, the majority of mass loss due to abrasion was from the cement paste, as opposed to the aggregate. Generally, for each test, cycle 1 shows the greatest amount of mass loss. The general decrease in measured mass loss for each subsequent cycle indicates that as the depth of wear gets larger, the presence of aggregate begins to take effect. This would explain why the SCC mixes showed a decrease in abrasion resistance relative to their conventional concrete equivalents.

5. HVFA RESULTS AND DISCUSSION

5.1. SHRINKAGE

5.1.1. Results. Figures 5.1 – 5.3 show the experimental data obtained from shrinkage tests of HVFA plotted with the various prediction models discussed in Section 2. Figure 5.4 shows the experimental results of all four mixes plotted with one another. In figures where different data sources are together, the source of the data can be found in parentheses after the data label in the legend of its respective figure. For all specimens tested for this study, the notation (S&T) will be used.

5.1.2. Discussion and Conclusions. For both HVFA mixes, results were very consistent with data from numerous previous research projects described in sections 2.6.1 – 2.6.4. It was expected that the two HVFA mixes would experience a decrease in shrinkage strain relative to the conventional mix. It was also expected that HVFA-L, due to the lower level of cementitious material, would experience a further decrease in shrinkage strains.

Both HVFA-H and HVFA-L showed a significant decrease in shrinkage strain relative to HVFA-C. Therefore, for use in practice when shrinkage is a design concern, both HVFA mixes are superior to their equivalent conventional concrete mix.

When comparing results to previous studies, both HVFA-H and HVFA-L performed as expected. Figures 5.5 – 5.6 show the results of HVFA-H and HVFA-L plotted against shrinkage results from Marlay (2011) and Atis (2003) both of which tested HVFA specimens with 70% replacement of Portland cement with fly ash, in addition to two mixes with 50% replacement for comparison. The results from Marlay and Atis validate the relatively low shrinkage strains experienced by HVFA-H and

HVFA-L compared to conventional concrete. Both databases together with experimental results are shown in **Figure 5.7**.




Figure 5.1 - HVFA-C Shrinkage Results and Prediction Models




Figure 5.2 - HVFA-H Shrinkage Results and Prediction Models




Figure 5.3 - HVFA-L Shrinkage Results and Prediction Models




Figure 5.4 – HVFA Shrinkage Results (Best fit Logarithmic)




Figure 5.5 – HVFA Shrinkage Results Compared to Marlay (2011)




Figure 5.6 – HVFA Shrinkage Results Compared to Atis (2003)




Figure 5.7 – HVFA Results with Shrinkage Databases

5.2. CREEP

5.2.1. Results. Creep Results are shown in Table 5.1.

Table 5.1 - Summary of HVFA Creep Results

Creep Strain (microstrain)				
Specimen	Days After Loading			
	7	14	56	126
HVFA-C	296	397	707	1070
HVFA-H	256	333	596	791
HVFA-L	178	225	377	489
Percentage of 126 Day Creep				
HVFA-C	28	37	66	100
HVFA-H	32	42	75	100
HVFA-L	36	46	77	100
Measured Creep Coefficient				
HVFA-C	0.464	0.622	1.12	1.68
HVFA-H	0.463	0.603	1.08	1.43
HVFA-L	0.421	0.533	0.893	1.16
Specific Creep ($\mu\epsilon/\text{psi}$)				
HVFA-C	0.137	0.184	0.327	0.496
HVFA-H	0.206	0.269	0.481	0.638
HVFA-L	0.128	0.162	0.271	0.351

Conversion: 1 MPa = 145.04 psi

5.2.2. Discussion and Conclusions. With the exception of HVFA-H in terms of specific creep, both HVFA specimens outperformed the conventional concrete specimens in creep testing. Both HVFA specimens experienced significantly less creep strain at 126 days after loading than the conventional concrete mix. Creep strain data may be misleading due to the fact that HVFA specimens were loaded at lower levels than conventional concrete due to their decreased compressive strengths at the time of loading. To normalize results, specific creep can be examined. As mentioned above, HVFA-H performed poorly in creep when taken in terms of specific creep. As the specimens got older, however, specific creep of HVFA-H got closer to that of HVFA-C.

At early ages, all three mixes tested showed similar behavior under load, however as the specimens got older, the advantage of HVFA over conventional concrete became more clear. This is demonstrated best by the percentage of 126 day creep. The data shows that during the first two weeks of loading, the HVFA specimens experienced a greater percentage of their ultimate creep strain than did the conventional concrete specimens. However, due to HVFA's tendency to gain strength at later ages, creep performance improved as the specimens got older.

This late age improvement in creep behavior is exactly what was discovered by Lane and Best, as summarized in ACI 232.2R-03. It was determined that since HVFA had a lower strength at time of loading with increase in strength gain as it aged, its creep behavior would be superior to that of conventional concrete. Additionally, it was shown that concrete with fly ash which had the same strength as conventional concrete still produced less creep at all ages. These properties of creep of HVFA were again confirmed by the results gained in this study.

5.3. ABRASION RESISTANCE

The following sections contain all measured data resulting from abrasion resistance testing along with discussions and conclusions.

5.3.1. Results. **Figures 5.8 – 5.10** show the mass losses recorded after each abrasion cycle for each mix tested. **Figures 5.11 – 5.12** show the relative abrasion resistance of each HVFA specimen by age. **Figures 5.13 -5.14** show the results of all specimens tested together. **Table 5.2** shows a summary of all results along with measured 28 day compressive strength.




Figure 5.8 - HVFA-C Mass Loss Results




Figure 5.9 - HVFA-H Mass Loss Results




Figure 5.10 - HVFA-L Mass Loss Results




Figure 5.11 - HVFA Average Depth of Wear by Age




Figure 5.12 - HVFA Average Mass Loss by Age




Figure 5.13 - HVFA Mass Loss Results




Figure 5.14 - HVFA Depth of Wear Results

Table 5.2 - Average Mass Loss Shown with 28 Day Compressive Strength

	HVFA-C	HVFA-H		HVFA-L	
28 Day Compressive Strength (psi)	5,400	3,100		3,500	
Age (days)	28	28	70	28	70
Avg. Mass Loss (g)	6.06	12.98	10.83	18.2	14.2
Avg. Depth of Wear (mm)	1.05	1.94	1.23	2.60	2.19

Conversion: 1 MPa = 145.04 psi
 1 lb. = 453.59 g
 1 in. = 25.4 mm

5.3.2. Discussion and Conclusions. Results are very consistent with findings by both Naik and Atis. The compressive strength of the concrete seems to have the most influence on its abrasion resistance. The two HVFA mixes showed significantly less resistance to abrasion than HVFA-C. This can be attributed to the lower

compressive strengths of the HVFA relative to HVFA-C. When comparing the two HVFA mixes to each other, however, compressive strength does not seem to be as indicative of abrasion resistance. The results suggest that at identical levels of fly ash replacement, abrasion resistance is more affected by volume of cementitious material rather than compressive strength, however more testing is warranted to confirm this. Because the lower relative resistance to abrasion of HVFA is most likely due to its strength, and not necessarily the fly ash replacement level, it is difficult to make conclusive findings on the effect of fly ash replacement on abrasion resistance without a larger scale investigation. As shown in **Figures 5.10 -5.11**, the abrasion resistance of both HVFA mixes did increase with age. This suggests that, at later ages when HVFA reaches improved strength, its abrasion resistance could be similar to that of conventional concrete, although further testing would be needed.

APPENDIX A.
SHRINKAGE DATA WITH RELATIVE HUMIDITY DATA




Figure A.1 – C6-58L shrinkage data shown with recorded relative humidity




Figure A.2 - S6-48L shrinkage data shown with recorded relative humidity




Figure A.3 – C10-58L shrinkage data shown with recorded relative humidity




Figure A.4 – S10-48L shrinkage data shown with recorded relative humidity




Figure A.5 – HVFA-C shrinkage data shown with recorded relative humidity




Figure A.6 – HVFA-H shrinkage data shown with recorded relative humidity




Figure A.7 – HVFA-L shrinkage data shown with recorded relative humidity

APPENDIX B.
EXAMPLE STRAIN CALCULATIONS

	A	B	C	D	E	F	G
1			Example Shrinkage and Creep Calculation				
2							
3			G= 0.40 x 10 ⁻⁵ (mm/mm)				
4			G= 4.00 x 10 ⁻⁶ (mm/mm)				
5							
6					Measured Data		
7			Specimen	Reading			
8			Refer Bar		2525	2524	2525
9			C6-58L SH1	1--1	2130	2111	2106
10			C6-58L SH1	1--2	3633	3615	3611
11			C6-58L SH1	1--3	4018	4002	3998
12			C6-58L SH1	2--1	2549	2531	2529
13			C6-58L SH1	2--2	3179	3162	3162
14			C6-58L SH1	2--3	3230	3213	3210
15			C6-58L SH1	3--1	5867	5846	5846
16			C6-58L SH1	3--2	1980	1962	1960
17			C6-58L SH1	3--3	2182	2166	2165
18							
19							
20					Calculated Strain		
21							
22			C6-58L SH1	1--1		-72	-24
23			C6-58L SH1	1--2		-68	-20
24			C6-58L SH1	1--3		-60	-20
25			C6-58L SH1	2--1		-68	-12
26			C6-58L SH1	2--2		-64	-4
27			C6-58L SH1	2--3		-64	-16
28			C6-58L SH1	3--1		-80	-4
29			C6-58L SH1	3--2		-68	-12
30			C6-58L SH1	3--3		-60	-8
31							
32			Average Shrinkage			-67.1	-13.3
33			Cumulative Shrinkage			-67.1	-80.4
34							

Figure B.1 – Example shrinkage and creep strain calculation

	A	B	C	D	E	F	G
1				Example Shrinkage and Creep Calculation			
2							
3			G= 0.4 x 10 ⁻⁵ (mm/mm)				
4			G= 4 x 10 ⁻⁶ (mm/mm)				
5							
6						Measured Data	
7			Specimen	Reading			
8			Refer Bar		2525	2524	2525
9			C6-58L SH1	1--1	2130	2111	2106
10			C6-58L SH1	1--2	3633	3615	3611
11			C6-58L SH1	1--3	4018	4002	3998
12			C6-58L SH1	2--1	2549	2531	2529
13			C6-58L SH1	2--2	3179	3162	3162
14			C6-58L SH1	2--3	3230	3213	3210
15			C6-58L SH1	3--1	5867	5846	5846
16			C6-58L SH1	3--2	1980	1962	1960
17			C6-58L SH1	3--3	2182	2166	2165
18							
19							
20						Calculated Strain	
21							
22			C6-58L SH1	1--1		=B5*(F9-E9)-(F8-E8))	=B5*(G9-F9)-(G8-F8))
23			C6-58L SH1	1--2		=B5*(F10-E10)-(F8-E8))	=B5*(G10-F10)-(G8-F8))
24			C6-58L SH1	1--3		=B5*(F11-E11)-(F8-E8))	=B5*(G11-F11)-(G8-F8))
25			C6-58L SH1	2--1		=B5*(F12-E12)-(F8-E8))	=B5*(G12-F12)-(G8-F8))
26			C6-58L SH1	2--2		=B5*(F13-E13)-(F8-E8))	=B5*(G13-F13)-(G8-F8))
27			C6-58L SH1	2--3		=B5*(F14-E14)-(F8-E8))	=B5*(G14-F14)-(G8-F8))
28			C6-58L SH1	3--1		=B5*(F15-E15)-(F8-E8))	=B5*(G15-F15)-(G8-F8))
29			C6-58L SH1	3--2		=B5*(F16-E16)-(F8-E8))	=B5*(G16-F16)-(G8-F8))
30			C6-58L SH1	3--3		=B5*(F17-E17)-(F8-E8))	=B5*(G17-F17)-(G8-F8))
31							
32			Average Shrinkage			=AVERAGE(F22:F30)	=AVERAGE(G22:G30)
33			Cumulative Shrinkage			=F32	=F33+G32
34							
35							

Figure B.2 – Example shrinkage and creep strain calculations with equations shown

APPENDIX C.
COEFFICIENT OF VARIATION DATA

C6-58L		Shrinkage														
Age (days)		2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
COV		0.20	0.62	0.46	0.25	0.74	0.41	0.25	0.62	0.42	0.45	9.57	0.28	0.25	7.83	1.21
		17	18	21	23	25	28	29	30	31	32	33	34	36	39	42
		0.25	6.75	0.27	0.19	0.36	0.17	1.94	1.11	5.25	0.82	0.72	0.18	0.53	1.38	0.58
		44	47	50	53	56	61	64	67	71	75	78	82	85	89	92
		0.51	0.59	0.28	0.53	0.38	0.61	0.17	0.22	0.20	0.57	0.31	0.53	0.41	0.62	0.55
		96	99	103	106	113	119	126	138	147	154					
		0.28	0.37	0.25	2.91	0.18	0.94	0.56	0.16	0.43	0.38					
		Creep														
Age (days after loading)					1	2	3	4	5	7	10	13	15	18	21	24
COV					0.60	0.55	0.89	0.87	0.21	0.48	1.04	0.46	0.43	0.40	0.39	0.43
		27	32	35	38	42	46	49	53	56	60	63	67	70	74	77
		0.32	0.45	0.22	3.68	1.22	3.35	0.33	1.37	0.63	0.62	0.46	1.02	0.45	0.34	0.54
		84	90	97	109	118	125									
		0.35	0.51	0.48	0.34	3.29	0.37									
		S6-48L														
		Shrinkage														
Age (days)		2	3	4	5	6	7	8	9	10	11	12	14	16	18	19
COV		0.50	0.45	0.31	0.48	0.74	0.21	0.16	0.65	0.24	0.24	0.13	0.16	0.10	0.51	0.37
		21	26	28	30	31	34	37	40	43	47	49	51	54	58	62
		0.26	0.31	0.21	3.74	0.36	0.18	0.18	0.48	0.18	0.21	1.01	0.27	0.20	0.14	0.42
		65	69	72	76	79	83	86	90	93	100	106	113	125	134	141
		0.77	6.64	0.40	0.66	0.58	0.32	0.31	0.19	0.00	0.17	0.53	0.90	0.17	0.16	0.16
		153														
		0.17														
		Creep														
Age (days after loading)					2	3	6	9	12	15	19	21	23	26	30	34
COV					0.92	0.21	0.18	0.17	0.22	0.15	0.13	0.43	0.62	2.29	0.11	1.66
		37	41	44	48	51	55	58	62	65	72	78	85	97	106	113
		0.41	0.42	1.56	1.03	0.89	2.71	0.47	0.54	0.85	0.42	0.56	0.52	0.95	3.30	0.35
		125														
		0.31														

Figure C.1 – C6-58L and S6-48L COV Data

C10-58L		Shrinkage														
Age (days)		2	3	4	5	6	10	11	12	13	14	15	18	21	24	27
COV		0.08	0.16	0.26	0.18	0.42	0.13	0.18	0.12	0.87	0.56	0.19	0.12	0.12	0.17	0.15
		28	30	31	33	35	38	41	45	48	52	55	59	62	66	69
		1.41	0.39	0.33	0.46	0.22	0.65	0.20	0.27	0.32	0.53	0.15	5.25	0.36	3.09	1.13
		73	76	83	90	97	109	119	126	137	147	157				
		0.40	1.56	0.16	3.09	0.61	0.11	0.21	0.10	1.24	0.92	0.25				
		Creep														
Age (days after loading)					2	3	5	7	10	13	17	20	24	27	31	34
COV					1.73	0.34	0.34	0.38	0.55	0.42	0.40	0.20	0.34	0.16	0.70	9.37
		38	41	45	48	55	62	69	81	91	98	109	119	129		
		1.89	0.49	0.21	0.62	0.17	0.29	0.21	0.17	0.58	0.14	0.27	0.20	0.14		
		S10-48L														
		Shrinkage														
Age (days)		2	3	5	6	7	8	9	12	14	15	19	24	27	28	29
COV		0.10	0.18	0.08	0.26	0.15	0.27	0.15	0.14	0.20	0.28	0.10	0.18	0.11	8.19	1.30
		30	33	36	40	47	54	61	68	74	82	89	96	104	113	120
		0.42	18.62	0.48	0.13	5.92	0.16	0.20	0.32	0.11	0.26	0.33	0.40	0.30	0.46	0.35
		131														
		0.87														
		Creep														
Age (days after loading)					1	2	5	8	12	19	26	33	40	46	54	61
COV					0.27	0.19	0.16	0.15	0.16	0.17	0.13	0.15	0.14	0.15	0.29	0.18
		68	76	85	92	103	126									
		0.4	0.18	9.27	0.22	0.13	0.45									

Figure C.2 – C10-58L and S10-48L COV Data

HVFA-C		Shrinkage														
Age (days)		2	3	4	5	6	7	8	9	13	14	16	18	21	24	27
COV		0.14	0.20	0.57	0.41	1.66	0.34	0.33	0.34	0.31	0.38	0.22	0.20	0.17	0.21	0.51
		28	29	30	34	36	38	41	44	48	51	55	58	62	65	69
		0.57	0.44	0.41	0.37	0.32	0.30	0.52	0.32	0.47	0.31	0.49	0.21	0.61	7.27	3.11
		72	76	79	86	93	100	112	122	129	140	150				
		0.34	0.34	0.36	1.48	1.69	0.20	0.13	0.43	0.10	0.36	0.36				
		Creep														
Age (days after loading)					1	2	6	8	10	13	16	20	23	27	30	34
COV					0.44	0.41	0.37	0.32	0.30	0.52	0.32	0.47	0.31	0.49	0.21	0.61
		37	41	44	48	51	58	65	72	84	94	101	112	122		
		7.27	3.11	0.34	0.34	0.36	1.48	1.69	0.20	0.13	0.43	0.10	0.36	0.36		
		HVFA-H														
		Shrinkage														
Age (days)		2	3	4	6	7	8	9	10	11	12	14	15	17	18	21
COV		0.46	0.22	0.15	0.19	0.37	0.39	0.42	0.54	1.29	1.13	0.42	0.60	1.07	0.16	0.20
		22	23	25	26	28	29	30	31	32	34	36	38	40	42	45
		1.03	0.38	0.47	0.60	1.17	3.09	4.24	0.14	1.50	0.23	0.24	1.04	2.36	0.94	0.77
		49	52	56	61	64	67	71	74	77	84	91	98	105	111	119
		0.75	0.21	0.36	0.40	0.23	1.08	0.26	0.33	0.36	1.97	0.49	0.31	1.63	0.16	0.24
		126	133	141	150											
		0.34	0.15	0.27	1.01											
		Creep														
Age (days after loading)					1	2	3	4	6	8	10	12	14	17	21	24
COV					0.49	0.81	0.90	0.31	0.25	0.22	0.51	1.31	0.67	0.33	0.37	0.30
		28	33	36	39	43	46	49	56	63	70	77	83	91	98	105
		0.21	0.66	0.21	0.35	0.16	0.25	0.30	0.36	0.26	0.19	0.21	0.10	1.59	1.08	5.28
		113	122													
		0.21	0.24													

Figure C.3 – HVFA-C and HVFA-H COV Data

HVFA-L		Shrinkage														
Age (days)		2	3	4	6	7	10	11	12	14	15	18	20	21	23	25
COV		0.25	0.27	0.35	0.29	0.16	0.15	0.57	0.26	0.22	0.67	0.42	0.83	2.88	0.19	0.36
		28	29	31	33	35	38	41	45	50	53	56	60	63	66	73
		1.70	0.47	10.22	0.78	0.13	0.36	0.37	0.47	0.37	0.24	2.45	0.25	0.54	0.39	1.64
		80	87	94	100	108	115	122	130	139	146	157				
		0.66	0.25	2.09	0.24	0.81	1.52	0.19	0.26	0.48	0.54	1.99				

		Creep														
Age (days after loading)					1	3	5	7	10	13	17	22	25	28	32	35
COV					0.56	0.37	0.37	0.28	0.66	0.24	0.21	0.47	0.37	0.40	0.17	0.55
		38	45	52	59	66	72	80	87	94	102	111	118	129		
		0.55	0.30	0.19	0.24	0.34	0.15	1.87	0.53	6.72	0.22	2.53	5.17	1.43		

Figure C.1 – HVFA-L COV Data

BIBLIOGRAPHY

- Alexander, K.M., Wardlaw, J., and Ivanusec, I. (1986). "A 4:1 Range in Concrete Creep When Cement SO₃ Content, Curing Temperature and Fly Ash Content are Varied." *Cement and Concrete Research*, Vol. 16, 173-180.
- American Coal Ash Association (ACAA) (2010). "2010 Coal Combustion Product (CCP) Production & Use Survey Report." ACAA, Aurora, Colorado.
- American Concrete Institute (ACI 116R-00) (2000), "Cement and Concrete Terminology." American Concrete Institute, Detroit, Michigan.
- American Concrete Institute (ACI 209R-92) (1997), "Prediction of Creep, Shrinkage, and Temperature Effects in Concrete Structures." American Concrete Institute, Detroit, Michigan.
- American Concrete Institute (ACI 209.1R-05) (2005), "Report on Factors Affecting Shrinkage and Creep of Hardened Concrete." American Concrete Institute, Detroit, Michigan.
- American Concrete Institute (ACI 232.2R-03) (2003), "Use of Fly Ash in Concrete." American Concrete Institute, Detroit, Michigan.
- American Concrete Institute (ACI 237R-07) (2007), "Self-Consolidating Concrete." American Concrete Institute, Detroit, Michigan.
- American Concrete Institute (ACI 318-08) (2008), "Building Code Requirements for Structural Concrete and Commentary." American Concrete Institute, Detroit, Michigan.
- ASTM C31/C31 M-09 (2009). "Standard Practice for Making and Curing Concrete Test Specimens in the Field." American Society for Testing and Materials, West Conshohocken, Pennsylvania.
- ASTM C39/C39 M-05 (2005). "Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens." American Society for Testing and Materials, West Conshohocken, Pennsylvania.
- ASTM C157/C157 M-08 (2008). "Standard Practice for Length Change of Hardened Hydraulic-Cement Mortar and Concrete." American Society for Testing and Materials, West Conshohocken, Pennsylvania.
- ASTM C3512/C512 M-10 (2010). "Standard Practice for Creep of Concrete in Compression." American Society for Testing and Materials, West Conshohocken, Pennsylvania.

- ASTM C944/C944 M-99 (2005). "Standard Practice for Abrasion Resistance of Concrete of Mortar Surfaces by the Rotating-Cutter Method." American Society for Testing and Materials, West Conshohocken, Pennsylvania.
- Atis, C.D. (2002). "High Volume Fly Ash Abrasion Resistant Concrete." *Journal of Materials in Civil Engineering*, May/June 2002, 274-277.
- Atis, C.D. (2003). "High-Volume Fly Ash Concrete with High Strength and Low Drying Shrinkage." *Journal of Materials in Civil Engineering*, March/April 2003, 153-156.
- Bazant, Z. P. and Baweja, S. (2000). "Creep and Shrinkage Prediction Model for Analysis and Design of Concrete Structures: Model B3" Adam Neville Symposium: Creep and Shrinkage—Structural Design Effects, ACI SP-194, A.Al-Manaseer, ed., Am. Concrete Institute, Farmington Hills, Michigan, 2000, 1-83.
- Comite Euro – International Du Beton (CEB) (1990), "CEB-FIP Model Code 1990" Thomas Telford, 1990-1993, 53-58.
- Fernandez-Gomez, J. and Landsberger, G.A. (2007). "Evaluation of Shrinkage Prediction Models for Self-Consolidating Concrete." *ACI Materials Journal*, October 2007, 464-473.
- Freyermuth, C.L. (1969). "Design of Continuous Highway Bridges with Precast, Prestressed Concrete Girders." *Journal of the Prestressed Concrete Institute*, Vol. 14, No. 2, 14-39.
- Gao, P., et. al. (2006). "Effect of Fly Ash on Deformation of Roller-Compacted Concrete." *ACI Materials Journal*, October 2006, 336-339.
- Gardner, N.J., and Lockman, M.J. (2001), "Design Provisions for Drying Shrinkage and Creep of Normal-Strength Concrete" *ACI Materials Journal*, 159-167.
- Holschemacher, K (2004). "Hardened Material Properties of Self-Compacting Concrete" *Journal of Civil Engineering and Management*, Vol X, No 4, 261-266.
- Khayat, K.H., and Mitchell, D. (2009). "Self-Consolidating Concrete for Precast, Prestressed Concrete Bridge Elements." National Cooperative Highway Research Program Report 628, Transportation Research Board, Washington, D.C.
- Long, W., Khayat, K.H., and Xing, F. (2011). "Autogenous Shrinkage of Prestressed Self-Consolidating Concrete." *The Open Civil Engineering Journal*, 2011, 5, 116-123.

- Long, et. al. (2011). "Statistical models to predict fresh and hardened properties of self-consolidating concrete." RILEM Materials and Structures, 2001.
- Marlay, K.M., (2011). "Hardened Concrete Properties and Durability Assessment of High Volume Fly Ash Concrete." M.S. Thesis, Missouri University of Science and Technology, Rolla, MO.
- Myers, J.J., Carrasquillo, R.L. (1999). "The Production and Quality Control of High Performance Concrete in Texas Bridge Structures," Center for Transportation Research, Report Number 580-589-1, November 1999, pp 564.
- Myers, J.J. and Yang, Y. "High Performance Concrete for Bridge A6130-Route 421 Pemiscot County, MO." UTC R39.
- Naik, T.R., Singh, S.S., and Ramme, B.W. (2002). "Effect of Source of Fly Ash on Abrasion Resistance of Concrete." Journal of Materials in Civil Engineering, September/October 2002, 417-426.
- Nath, P. and Sarker, P. (2011). "Effect of Fly Ash on the Durability Properties of High Strength Concrete." Procedia Engineering, 14 (2011), 1149-1156.
- Ortega, C.A., (2012). "Shear and Fracture Behavior of High-Volume Fly Ash Reinforced Concrete for Sustainable Construction." PhD Dissertation, Missouri University of Science and Technology, Rolla, MO.
- Perenchio, W.F., (1997). "The Drying Shrinkage Dilemma-Some Observations and Questions About Drying Shrinkage and its Consequence," *Concrete Construction*, V. 42, No. 4, pp. 379-383.
- Schindler, A.K., et. al. (2007). "Properties of Self-Consolidating Concrete for Prestressed Members." ACI Materials Journal, January-February 2007, 53-61.
- Tadros, M.K., Al-Omaishi, N., Seguirant, S.J., and Gallt, J.G. (2003). "Prestress Losses in Pretensioned High-Strength Concrete Bridge Girders." National Cooperative Highway Research Program Report 496, Transportation Research Board, National Research Council, Washington, D.C.
- Termkhajornkit, P., et.al. (2005). "Effect of Fly Ash on Autogenous Shrinkage." Cement and Concrete Research, 35 (2005), 473-482.
- U.S. Green Building Council (USGBC) (2009). "LEED Reference Guide for Green Building and Construction." USGBC, Washington, D.C., 369-377.

VITA

Brian Timothy Tucker was born in St. Louis, MO. Brian graduated in May 2006 from St. Dominic High School in O'Fallon, MO. Following graduating, he attended the Missouri University of Science and Technology (Missouri S&T). In December 2010 he received his B.S. degree in Civil Engineering, graduating Magna Cum Laude. In January 2011 he enrolled in the M.S. Civil Engineering program at Missouri S&T with an emphasis in Structural Engineering. In August 2012 he graduated from Missouri S&T with his M.S. degree in Civil Engineering. While at Missouri S&T, he was a four year varsity soccer player, competing in the NCAA Division II Great Lakes Valley Conference (GLVC).